



		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		STAGING PLAN		P0 Box 554 Beaudesert QLD 4285		 <b>ACS Engineers</b> CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT		
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				(07) 5541 3500 www.acsengineers.com.au				
		MAP GRID		HAACK - SANDY CREEK ROAD		ENGINEERING CERTIFICATION (RPEQ)		DRAWING NUMBER		REVISION		
3	INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		#	FIELD	NAME	SIGNATURE	DATE	ACS-230008-GEN-03	3
2	FOR APPROVAL	MS	23/06/2023			13697	CIVIL	S. SHAY		21/12/23		
1	PRELIMINARY	MA	19/04/2023	MA	02/2023							
REVISION/DETAILS		DWN	DATE	DES	DATE							
FILE: C:\1205\DATA\ACSS\YN\230008 HAACK - SANDY CREEK ROAD_015\DESIGN\DRAWING FILES\ACS-230008-GEN.DWG PLOT TIME: 21/12/2023 - 12:11PM BY USER: NICHOLAS FALVEY												





PLANS AND DOCUMENTS referred to in the SDA APPROVAL

SDA approval: AP2023/005





REVISION/DETAILS		DWN	DATE	DES	DATE
3	INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	MA	02/2023
2	FOR APPROVAL	MS	23/06/2023		
1	PRELIMINARY	MA	19/04/2023		

SURVEY DATA	
DATUM	MATT HAACK - HAACK LOGISTICS GROUP
MAP GRID	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285
HEIGHT ORIGIN	HAACK - SANDY CREEK ROAD
SURVEY BOOKS	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285

OVERALL SITE LAYOUT PLAN			
ENGINEERING CERTIFICATION (RPEQ)			
#	FIELD	NAME	DATE
13697	CIVIL	S. SHAY	21/12/23


P.O. Box 554 Beaudesert QLD 4285 (07) 5541 3500 www.acsengineers.com.au		 CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT
DRAWING NUMBER	REVISION	
ACS-230008-GEN-04	3	





PLANS AND DOCUMENTS referred to in the SDA APPROVAL

SDA approval: AP2023/005





REVISION/DETAILS		DATE	BY	DATE
3	INCLUSION OF SHED LAYOUT PLAN	24/11/2023	MLS	
2	FOR APPROVAL	23/06/2023	MS	
1	PRELIMINARY	19/04/2023	MA	02/2023

SURVEY DATA	
MATT HAACK - HAACK LOGISTICS GROUP	
590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285	
HAACK - SANDY CREEK ROAD	
590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285	

ENGINEERING CERTIFICATION (RPEQ)			
#	FIELD	NAME	DATE
13697	CIVIL	S. SHAY	21/12/23

P.O. Box 554 Beaudesert QLD 4285 (07) 5541 3500 www.acsengineers.com.au		 CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT
DRAWING NUMBER	REVISION	
ACS-230008-GEN-05	3	





Truck and Dog (19m)  
 Overall Length 19.000m  
 Overall Width 2.500m  
 Overall Body Height 3.738m  
 Min Body Ground Clearance 0.417m  
 Track Width 2.500m  
 Lock-to-lock time 5.00s  
 Curb to Curb Turning Radius 12.640m




**PLANS AND DOCUMENTS referred to in the SDA APPROVAL**

SDA approval: AP2023/005



		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		P0 Box 554 Beaudesert QLD 4285		 CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT					
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		DETAILED LAYOUT PLAN - STAGE 2							
		MAP GRID		HAACK - SANDY CREEK ROAD		ENGINEERING CERTIFICATION (RPEQ)		DRAWING NUMBER					
3		INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		#	FIELD	NAME	SIGNATURE	DATE	REVISION	
2		FOR APPROVAL	MS	23/06/2023			13697	CIVIL	S. SHAY		21/12/23	ACS-230008-GEN-06	
1		PRELIMINARY	MA	19/04/2023	MA	02/2023					3		
		REVISION/DETAILS		DWN		DATE		DES		DATE			






PLANS AND DOCUMENTS referred to in the SDA APPROVAL

SDA approval: AP2023/005

		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		HARDSTAND & SHED LAYOUT		P0 Box 554 Beaudesert QLD 4285		ACS Engineers CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				(07) 5541 3500 www.acsengineers.com.au		
		MAP GRID		HAACK - SANDY CREEK ROAD		ENGINEERING CERTIFICATION (RPEQ)		DRAWING NUMBER		REVISION
		HEIGHT ORIGIN		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		# FIELD NAME SIGNATURE DATE		ACS-230008-GEN-07		1
2	FOR APPROVAL	MS	23/06/2023			13697	CIVIL	S. SHAY	21/12/23	
1	PRELIMINARY	MA	02/02/2023	MA	02/2023					
REVISION/DETAILS		DWN	DATE	DES	DATE					
FILE: C:\1205\DATA\ACSS\230008 HAACK - SANDY CREEK ROAD_015\DESIGN\DRAWING FILES\ACS-230008-GEN.DWG PLOT TIME: 21/12/2023 - 12:18PM BY USER: NICHOLASFALVEY										






SIGHT DISTANCE REQUIREMENTS (EDD) - NORTHBOUND

CHECK CASE	VEHICLE	TIME OF DAY	V (km/hr)	h1 (m)	h2 (m)	Of (s)	Rt (s)	d	GRADE (%)	SISD (m)	COMMENTS
N1	CAR	DAY	80	1.10	1.25	3.00	2.00	0.36	-0.50	133	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
N2	CAR	NIGHT 1	80	0.65	1.25	2.60	2.00	0.46	-0.50	113	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
N3	CAR	NIGHT 2	80	1.10	0.80	2.50	2.00	0.46	-0.50	144	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
N4	TRUCK	DAY	80	2.40	1.25	3.00	2.00	0.24	-0.50	133	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
N5	TRUCK	NIGHT 1	80	1.05	1.25	1.80	2.00	0.29	-0.50	166	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
N6	TRUCK	NIGHT 2	80	2.40	0.80	0.80	2.00	0.29	-0.50	148	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)


SIGHT DISTANCE REQUIREMENTS (EDD) - SOUTHBOUND


CHECK CASE	VEHICLE	TIME OF DAY	V (km/hr)	h1 (m)	h2 (m)	Of (s)	Rt (s)	d	GRADE (%)	SISD (m)	COMMENTS
S1	CAR	DAY	80	1.10	1.25	3.00	2.00	0.36	1.50	131	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
S2	CAR	NIGHT 1	80	0.65	1.25	2.60	2.00	0.46	1.50	111	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
S3	CAR	NIGHT 2	80	1.10	0.80	2.50	2.00	0.46	1.50	142	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
S4	TRUCK	DAY	80	2.40	1.25	3.00	2.00	0.24	1.50	130	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
S5	TRUCK	NIGHT 1	80	1.05	1.25	1.80	2.00	0.29	1.50	160	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)
S6	TRUCK	NIGHT 2	80	2.40	0.80	3.00	2.00	0.29	1.50	143	SIGHT DISTANCE AVAILABLE MEETS REQUIRED SISD (EDD)




PLANS AND DOCUMENTS referred to in the SDA APPROVAL

SDA approval: AP2023/005



		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		PROPERTY ACCESS DETAIL		P0 Box 554 Beaudesert QLD 4285		 CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT	
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				(07) 5541 3500 www.acsengineers.com.au			
		MAP GRID		HAACK - SANDY CREEK ROAD				DRAWING NUMBER		REVISION	
3		INCLUSION OF SHED LAYOUT PLAN		MLS 24/11/2023				ENGINEERING CERTIFICATION (RPEQ)			
2		FOR APPROVAL		MS 23/06/2023				#			
1		PRELIMINARY		MA 02/02/2023		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		FIELD			
		REVISION/DETAILS		DWN DATE				NAME			
		DATE		DES DATE				SIGNATURE			
		FILE: C:\1205\DATA\ACSS\YN\230008 HAACK - SANDY CREEK ROAD_015\DESIGN\DRAWING FILES\ACS-230008-GEN.DWG		PLOT TIME: 21/12/2023 - 12:18PM		BY USER: NICHOLAS FALVEY		DATE		21/12/23	
								S. SHAY		ACS-230008-GEN-08	
										3	





CUT/FILL DEPTH RANGE			
NO.	MIN. LEVEL	MAX. LEVEL	COLOUR
1	-5.000	-4.000	Red
2	-4.000	-3.000	Orange
3	-3.000	-2.000	Yellow
4	-2.000	-1.000	Light Yellow
5	-1.000	0.000	Yellow
6	0.000	1.000	Light Blue
7	1.000	2.000	Blue
8	2.000	3.000	Dark Blue
9	3.000	4.000	Very Dark Blue
10	4.000	5.000	Dark Purple
11	5.000	6.000	Very Dark Purple

STRIPPING VOLUME:  
PROPOSED PAD:

CUT VOLUME = 9459.6m<sup>3</sup>  
FILL VOLUME = 9606.5m<sup>3</sup>

NET: 146.9m<sup>3</sup> (EXCESS FILL)



PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005

		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		BULK EATHWORKS PLAN - STAGE 1			P0 Box 554 Beaudesert QLD 4285		ACS Engineers	
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285					(07) 5541 3500 www.acsengineers.com.au		CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT	
		MAP GRID		HAACK - SANDY CREEK ROAD					DRAWING NUMBER		REVISION	
		HEIGHT ORIGIN		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285					ACS-230008-GEN-09		3	
		SURVEY BOOKS										
3	INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	MA	02/2023	ENGINEERING CERTIFICATION (RPEQ)						
2	FOR APPROVAL	MS	23/06/2023	DES		#	FIELD	NAME	SIGNATURE	DATE		
1	PRELIMINARY	MA	19/04/2023	DES		13697	CIVIL	S. SHAY		21/12/23		
REVISION/DETAILS		DWN	DATE	DES	DATE							






PLANS AND DOCUMENTS referred to in the SDA APPROVAL




SDA approval: AP2023/005

SITE SECTION 'SECTION A-A'



SITE SECTION 'SECTION B-B'



SITE SECTION 'SECTION C-C'

		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		<p>PO Box 554 Beaudesert QLD 4285</p> <p>(07) 5541 3500 www.acsengineers.com.au</p> <p><b>ACS Engineers</b> CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT</p>		<p>SECTIONS</p> <p>ENGINEERING CERTIFICATION (RPEQ)</p> <table border="1"> <tr><th>#</th><th>FIELD</th><th>NAME</th><th>SIGNATURE</th><th>DATE</th></tr> <tr><td>13697</td><td>CIVIL</td><td>S. SHAY</td><td></td><td>21/12/23</td></tr> </table>			#	FIELD	NAME	SIGNATURE	DATE	13697	CIVIL	S. SHAY		21/12/23
#	FIELD	NAME	SIGNATURE	DATE																
13697	CIVIL	S. SHAY		21/12/23																
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285																
		MAP GRID																		
3		INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	HAACK - SANDY CREEK ROAD		DRAWING NUMBER		ACS-230008-GEN-10		REVISION		3							
2		FOR APPROVAL	MS	23/06/2023																
1		PRELIMINARY	MA	19/04/2023																
REVISION/DETAILS				DATE		DES		DATE												

FILE: C:\1205\DATA\ACSS\230008 HAACK - SANDY CREEK ROAD\_615\DESIGN\DRAWING FILES\ACS-230008-GEN.DWG PLOT TIME: 21/12/2023 - 12:18PM BY USER: NICHOLAS FALVEY



**LANDSCAPE BUFFER**

1. LANDSCAPE BUFFER TO BE 5M WIDE.
2. SPACING SHOULD RESULT IN PROMOTING QUICK VERTICAL GROWTH TO SHADE OUT WEED COMPETITION.
3. LANDSCAPING BUFFER (8m WIDE) TO BE PLANTED (MINIMUM PLANTING DENSITY OF ONE (1) TREE OR SHRUB PER 16M<sup>2</sup>) WITH A MIXTURE OF UNDERSTOREY (SHRUB) AND OVERSTORY (TREE) SPECIES ENDEMIC TO THE LOCAL REGIONAL ECOSYSTEM CONSISTING OF:  
 INSIDE ROW - LEPTOSPERMYM PETERSONII (EST. HEIGHT 4-5MN)  
 MIDDLE ROW - MELALEUCA LINARIFOLIA (EST. HEIGHT 10M)  
 OUTSIDE ROW - EUCALYPTUS MELANOPHLOIA (EST. HEIGHT 20M)



**OTHER SUITABLE ALTERNATIVES INCLUDE:**

- EUCALYPTUS MOLUCCANA
- ANGOPHORA FLORIBUNDA
- CORYMBIA DARKSONIANA
- LOPHOSTEMEN SUAVEOLENS
- MELALEUCA BRACTEATA
- MELALEUCA TRICHOSTACHYA

4. 750MM TREES AND 500MM SHRUBS ARE TO BE PLANTED AS DETAILED IN INSET
5. BUFFER AREA TO BE FENCED TO PROTECT TREES FROM CATTLE
6. PLANTS TO BE MAINTAINED UNTIL ESTABLISHED. FAILURES TO BE REPLACED.


**PLANTING REQUIREMENTS**

1. **MULCHING**
  - A. LAY ORGANIC MULCH SUCH AS HOOP PINE FINES OR SIMILAR (TO MEET AS4454-2003) TO PROTECT BARE SOIL, RETAIN SOIL MOISTURE AND SUPPRESS WEED RE-GROWTH.
  - B. ENSURE MULCH IS FREE OF WEED SEED OR FOREIGN OBJECTS.
  - C. SPREAD TO A DEPTH OF 100MM - 150MM AND ALLOW TO SETTLE FOR 4 WEEKS BEFORE PLANTING SEEDLINGS).
  - D. SPOT SPRAY EMERGING WEEDS AS NECESSARY.
2. **PLANTING**
  - A. RAKE AWAY AN AREA OF MULCH (MIN 300MM X 300MM) TO EXPOSE THE SOIL.
  - B. DIG A HOLE AT LEAST TWICE THE SIZE OF THE TUBE / POT (MIN 300MM X 300MM X 200MM DEEP)
  - C. DISTURB THE SURROUNDING SUBSTRATE UP TO 100MM TO AVOID LEAVING 'CLEAN' SIDES AND BASE OF THE HOLE PARTICULARLY WHEN AN AUGER HAS BEEN USED TO DIG THE HOLE.
  - D. POUR 5-6 LITERS OF WATER INTO THE HOLE AND ALLOW TO DRAIN FREELY.
  - E. ADD SLOW RELEASE FERTILISER AND SOIL WETTING AGENT TO THE BASE OF THE WELL AND COVER WITH A SMALL AMOUNT OF EXISTING SOI, OR MIX IN WITH THE SOIL TO BE PLACED BACK AROUND THE PLANT. AVOID ANY CONTACT OF THE FERTILISER AND SOIL WETTING AGENT WITH THE PLANT ROOTS.
  - F. PLANT THE SEEDLING SLIGHTLY BELOW THE SOIL LEVEL AND BACK FILL THE HOLE WITH EXISTING SOIL COVERING THE TOP OF THE POTTING MIX. CREATE A SMALL WELL TO CATCH WATER.
  - G. REPLACE MULCH AROUND THE PLANT. ENSURE NO MULCH TOUCHES THE BASE OF THE TRUNK, MAINTAINING A SPACE OF 50-100MM BETWEEN MULCH AND TRUNK.
  - H. ERECT A 'GROWTUBE' AROUND EACH PLANT, REMOVE GROWTTUBES WHEN PLANTS ARE AT 1.5 TIMES THE HEIGHT OF THE GROWTUBE.
  - I. WATER EACH PLANT THOROUGHLY WITHIN 1 HOUR OF PLANTING.
3. **WATERING**
  - A. FOLLOW-UP WATERING SHOULD CONSIST OF:
    - ONCE PER WEEK - FOR THE FIRST 4 WEEKS
    - ONCE PER FORTNIGHT - FOR 4 TO 6 WEEKS
    - ONCE PER MONTH - FOR 3 TO 6 MONTHS



		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		LANDSCAPE PLAN		P.O. Box 554 Beaudesert QLD 4285		ACS Engineers CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT			
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				(07) 5541 3500 www.acsengineers.com.au		DRAWING NUMBER			
		MAP GRID		HAACK - SANDY CREEK ROAD				ENGINEERING CERTIFICATION (RPEQ)		REVISION			
3		INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		#	FIELD	NAME	SIGNATURE	DATE	ACS-230008-GEN-11	3
2		FOR APPROVAL	MS	23/06/2023			13697	CIVIL	S. SHAY	<i>S. Shay</i>	21/12/23		
1		PRELIMINARY	MA	19/04/2023									
		REVISION/DETAILS		DATE		DES		DATE					
		DWN		DATE		DES		DATE					
FILE: C:\11205\DATA\ACSS\230008 HAACK - SANDY CREEK ROAD_015\DESIGN\DRAWING FILES\ACS-230008-GEN.DWG PLOT TIME: 21/12/2023 - 12:18PM BY USER: NICHOLASFALVEY													





**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**

**SDA approval: AP2023/005**



REVISION/DETAILS		DWN	DATE	DES	DATE
3	INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	MA	02/2023
2	FOR APPROVAL	MS	23/06/2023		
1	PRELIMINARY	MA	19/04/2023		

SURVEY DATA	
DATUM	MATT HAACK - HAACK LOGISTICS GROUP
MAP GRID	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285
HEIGHT ORIGIN	HAACK - SANDY CREEK ROAD
SURVEY BOOKS	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285

STORMWATER MANAGEMENT PLAN			
ENGINEERING CERTIFICATION (RPEQ)			
#	FIELD	NAME	DATE
13697	CIVIL	S. SHAY	21/12/23

P0 Box 554 Beaudesert QLD 4285 (07) 5541 3500 www.acsengineers.com.au	<b>ACS Engineers</b> CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT
DRAWING NUMBER	REVISION
ACS-230008-GEN-12	3



**SEDIMENT AND EROSION CONTROL – GENERAL NOTES:**

- ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MUST BE IMPLEMENTED AND A REVISED EROSION AND SEDIMENT CONTROL PLAN (ESCP) MUST BE SUBMITTED FOR APPROVAL IN THE EVENT THAT SITE CONDITIONS CHANGE SIGNIFICANTLY FROM THOSE CONSIDERED WITHIN THE ESCP.
- WHERE THERE IS A HIGH PROBABILITY THAT SERIOUS OR MATERIAL ENVIRONMENTAL HARM MAY OCCUR AS A RESULT OF SEDIMENT LEAVING THE SITE, APPROPRIATE ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MUST BE IMPLEMENTED SUCH THAT ALL REASONABLE AND PRACTICABLE MEASURES ARE BEING TAKEN TO PREVENT OR MINIMISE SUCH HARM. ONLY THOSE WORKS NECESSARY TO MINIMISE OR PREVENT ENVIRONMENTAL HARM SHALL BE CONDUCTED ON-SITE PRIOR TO APPROVAL OF THE AMENDED EROSION AND SEDIMENT CONTROL PLAN (ESCP).
- IN CIRCUMSTANCES WHERE IT IS CONSIDERED NECESSARY TO PREPARE AN AMENDED EROSION AND SEDIMENT CONTROL PLAN (ESCP), AND WHERE THE DELIVERY OF SUCH AN AMENDED ESCP IS NOT IMMINENT, THEN ALL NECESSARY NEW OR MODIFIED EROSION AND SEDIMENT CONTROL WORKS MUST BE IN ACCORDANCE TO WITH IECA (2008) BEST PRACTICE EROSION & SEDIMENT CONTROL. UPON APPROVAL OF THE AMENDED ESCP ALL WORKS MUST BE IMPLEMENTED IN ACCORDANCE WITH THE AMENDED PLAN.

**SITE ACCESS:**

- PRIOR TO THE COMMENCEMENT OF SITE WORKS, THE LOCATION OF THE SITE ACCESS POINT MUST BE VERIFIED WITH RELEVANT AUTHORITY.
- SITE ACCESS IS RESTRICTED TO ONE LOCATION.
- SITE EXIT POINT MUST BE APPROPRIATELY MANAGED TO MINIMISE THE RISK OF SEDIMENT BEING TRACKED ONTO SEALED PUBLIC ROADWAYS.
- STORMWATER RUNOFF FROM ACCESS ROADS AND STABILISED ENTRY/EXIT POINTS MUST DRAIN TO AN APPROPRIATE SEDIMENT CONTROL DEVICE.

**SOIL AND STOCKPILE MANAGEMENT:**

- ALL REASONABLE AND PRACTICABLE MEASURES MUST BE TAKEN TO OBTAIN THE MAXIMUM BENEFIT FROM EXISTING TOPSOIL, INCLUDING:
  - WHERE THE PROPOSED AREA OF SOIL DISTURBANCE DOES NOT EXCEED 2500m<sup>2</sup>, AND THE TOPSOIL DOES NOT CONTAIN UNDESIRABLE WEED SEED, THE TOP 100mm OF SOIL LOCATED WITHIN AREAS OF PROPOSED SOIL DISTURBANCE (INCLUDING STOCKPILE AREAS) MUST BE STRIPPED AND STOCKPILED SEPARATELY FROM THE REMAINING SOIL.
  - WHERE THE PROPOSED AREA OF SOIL DISTURBANCE EXCEEDS 2500m<sup>2</sup>, AND THE TOPSOIL DOES NOT CONTAIN UNDESIRABLE WEED SEED, THE TOP 50mm OF SOIL MUST BE STRIPPED AND STOCKPILED SEPARATELY FROM THE REMAINING TOPSOIL, AND SPREAD AS A FINAL SURFACE SOIL.
  - IN AREAS WHERE THE TOPSOIL CONTAINS UNDESIRABLE WEED SEED, THE AFFECTED SOIL MUST BE SUITABLY BURIED OR REMOVED FROM THE SITE.
- STOCKPILES OF ERODIBLE MATERIAL THAT HAS THE POTENTIAL TO CAUSE ENVIRONMENTAL HARM IF DISPLACED MUST BE:
  - APPROPRIATELY PROTECTED FROM WIND, RAIN, CONCENTRATED SURFACE FLOW AND EXCESSIVE UP-SLOPE STORMWATER SURFACE FLOWS.
  - LOCATED AT LEAST 2m FROM ANY HAZARDOUS AREA, RETAINED VEGETATION OR CONCENTRATED DRAINAGE LINE.
  - LOCATED UP-SLOPE OF AN APPROPRIATE SEDIMENT CONTROL SYSTEM.
  - PROVIDED WITH AN APPROPRIATE PROTECTIVE COVER (SYNTHETIC, MULCH OR VEGETATIVE) IF THE MATERIALS ARE LIKELY TO BE STOCKPILED FOR MORE THAN 28 DAYS.
  - PROVIDED WITH AN APPROPRIATE PROTECTIVE COVER (SYNTHETIC, MULCH OR VEGETATIVE) IF THE MATERIALS ARE LIKELY TO BE STOCKPILED FOR MORE THAN 10 DAYS DURING THOSE MONTHS THAT HAVE A HIGH EROSION RISK.
  - PROVIDED WITH AN APPROPRIATE PROTECTIVE COVER (SYNTHETIC, MULCH OR VEGETATIVE) IF THE MATERIALS ARE LIKELY TO BE STOCKPILED FOR MORE THAN 5 DAYS DURING THOSE MONTHS THAT HAVE A EXTREME EROSION RISK.
- A SUITABLE FLOW DIVERSION SYSTEM MUST BE ESTABLISHED IMMEDIATELY UP-SLOPE OF A STOCKPILE OF ERODIBLE MATERIAL THAT HAS THE POTENTIAL TO CAUSE ENVIRONMENTAL HARM IF DISPLACED IF THE UP-SLOPE CATCHMENT AREA DRAINING TO THE STOCKPILE EXCEEDS 1500m<sup>2</sup>.

**DRAINAGE CONTROL:**

- ALL DRAINAGE CONTROL MEASURES MUST BE APPLIED AND MAINTAINED IN ACCORDANCE WITH THE CONSTRUCTION PLANS.
- WHEREVER REASONABLE AND PRACTICABLE, STORMWATER RUNOFF ENTERING THE SITE FROM EXTERNAL AREAS, AND NON-SEDIMENT LADEN (CLEAN) STORMWATER RUNOFF ENTERING A WORK AREA OR AREA OF SOIL DISTURBANCE, MUST BE DIVERTED AROUND OR THROUGH THAT AREA IN A MANNER THAT MINIMISES SOIL EROSION AND THE CONTAMINATION OF THAT WATER FOR ALL DISCHARGES UP TO THE SPECIFIED DESIGN STORM DISCHARGE.
- DURING THE CONSTRUCTION PERIOD, ALL REASONABLE AND PRACTICABLE MEASURES MUST BE IMPLEMENTED TO CONTROL FLOW VELOCITIES IN SUCH A MANNER THAN PREVENTS SOIL EROSION ALONG DRAINAGE PATHS AND AT THE ENTRANCE AND EXIT OF ALL DRAINS AND DRAINAGE PIPES DURING ALL STORMS UP TO THE RELEVANT DESIGN STORM DISCHARGE.
- TO THE MAXIMUM DEGREE REASONABLE AND PRACTICABLE, ALL WATERS DISCHARGED DURING THE CONSTRUCTION PHASE MUST DISCHARGE ONTO STABLE LAND, IN A NON-EROSIVE MANNER, AND AT A LEGAL POINT OF DISCHARGE.
- WHEREVER REASONABLE AND PRACTICABLE, "CLEAN" SURFACE WATERS MUST BE DIVERTED AWAY FROM SEDIMENT CONTROL DEVICES AND ANY UNTREATED, SEDIMENT-LADEN WATERS.
- DURING THE CONSTRUCTION PERIOD, ROOF WATER MUST BE MANAGED IN A MANNER THAT MINIMISES SOIL EROSION THROUGHOUT THE SITE, AND SITE WETNESS WITHIN ACTIVE WORK AREAS.
- DRAINS ARE TO BE SIZED AND CONSTRUCTED TO ALLOW WATER TO DRAIN. THIS MAY INCLUDE CUTTING INTO THE EARTH TO OBTAIN THE REQUIRED FALL TO PERMIT DRAINAGE. DIMENSIONS GIVEN ARE A MINIMUM.

**EROSION CONTROL:**

- ALL EROSION CONTROL MEASURES MUST BE APPLIED AND MAINTAINED IN ACCORDANCE WITH IECA (2008) BEST PRACTICE EROSION & SEDIMENT CONTROL.
- THE APPLICATION OF LIQUID-BASED DUST SUPPRESSION MEASURES MUST ENSURE THAT SEDIMENT-LADEN RUNOFF RESULTING FROM SUCH MEASURES DOES NOT CREATE A TRAFFIC OR ENVIRONMENTAL HAZARD.
- ALL TEMPORARY EARTH BANKS, FLOW DIVERSION SYSTEMS, AND EMBANKMENTS ASSOCIATED WITH CONSTRUCTED SEDIMENT BASINS MUST BE MACHINE-COMPACTED, SEEDED AND MULCHED FOR THE PURPOSE OF ESTABLISHING A TEMPORARY VEGETATIVE COVER WITHIN 10 DAYS AFTER GRADING.
- UNPROTECTED SLOPE LENGTHS MUST NOT EXCEED 80m, OR AN EQUIVALENT VERTICAL FALL OF 3m DURING THE CONSTRUCTION PERIOD.
- THE CONSTRUCTION AND STABILISATION OF EARTH BATTERS STEEPER THAN 6:1 (H:V) MUST BE STAGED SUCH THAT NO MORE THAN 3 VERTICAL-METRES OF ANY BATTER IS EXPOSED TO RAINFALL AT ANY INSTANT.
- SYNTHETIC REINFORCED EROSION CONTROL MATS AND BLANKETS MUST NOT BE PLACED WITHIN, OR ADJACENT TO, RIPARIAN ZONES AND WATERCOURSES IF SUCH MATERIALS ARE LIKELY TO CAUSE ENVIRONMENTAL HARM TO WILDLIFE OR WILDLIFE HABITATS.
- A MINIMUM 60% GROUND COVER MUST BE ACHIEVED ON ALL NON-COMPLETED EARTHWORKS EXPOSED TO ACCELERATED SOIL EROSION IF FURTHER CONSTRUCTION ACTIVITIES OR SOIL DISTURBANCES ARE LIKELY TO BE SUSPENDED FOR MORE THAN 30 DAYS DURING THOSE MONTHS WHEN THE EXPECTED RAINFALL IS LESS THAN 30mm; MINIMUM 70% COVER WITHIN 30 DAYS IF BETWEEN 30 AND 45mm; MINIMUM 70% COVER WITHIN 20 DAYS IF BETWEEN 45 AND 100mm; MINIMUM 75% COVER WITHIN 10 DAYS IF BETWEEN 100 AND 225mm; AND MINIMUM 80% COVER WITHIN 5 DAYS IF GREATER THAN 225mm. (ALTERNATIVE TO ABOVE)


**SEDIMENT CONTROL:**

- ALL SEDIMENT CONTROL MEASURES MUST BE APPLIED AND MAINTAINED IN ACCORDANCE WITH IECA (2008) BEST PRACTICE EROSION & SEDIMENT CONTROL.
- OPTIMUM BENEFIT MUST BE MADE OF EVERY OPPORTUNITY TO TRAP SEDIMENT WITHIN THE WORK SITE, AND AS CLOSE AS PRACTICABLE TO ITS SOURCE.
- SEDIMENT TRAPS MUST BE INSTALLED AND OPERATED TO BOTH COLLECT AND RETAIN SEDIMENT.
- THE POTENTIAL SAFETY RISK OF A PROPOSED SEDIMENT TRAP TO SITE WORKERS AND THE PUBLIC MUST BE GIVEN APPROPRIATE CONSIDERATION, ESPECIALLY THOSE DEVICES LOCATED WITHIN PUBLICLY ACCESSIBLE AREAS.
- ALL REASONABLE AND PRACTICABLE MEASURES MUST BE TAKEN TO PREVENT, OR AT LEAST MINIMISE, THE RELEASE OF SEDIMENT FROM THE SITE.
- SUITABLE ALL-WEATHER MAINTENANCE ACCESS MUST BE PROVIDED TO ALL SEDIMENT CONTROL DEVICES.
- SEDIMENT CONTROL DEVICES MUST BE DE-SILTED AND MADE FULLY OPERATIONAL AS SOON AS REASONABLE AND PRACTICABLE AFTER A SEDIMENT-PRODUCING EVENT, WHETHER NATURAL OR ARTIFICIAL, IF THE DEVICE'S SEDIMENT RETENTION CAPACITY FALLS BELOW 75% OF ITS DESIGN RETENTION CAPACITY.
- MATERIALS, WHETHER LIQUID OR SOLID, REMOVED FROM SEDIMENT CONTROL DEVICES DURING MAINTENANCE OR DECOMMISSIONING, MUST BE DISPOSED OF IN A MANNER THAT DOES NOT CAUSE ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.


**SITE REHABILITATION:**

- ALL DISTURBED AREAS IDENTIFIED AS VERY LOW, LOW, MEDIUM, HIGH, OR EXTREME EROSION RISK MUST BE SUITABLY STABILISED WITHIN 30, 30, 20, 10 OR 5 DAYS RESPECTIVELY, OR PRIOR TO ANTICIPATED RAINFALL, WHICHEVER IS THE GREATER, FROM THE DAY THAT SOIL DISTURBANCES ON THE AREA HAVE BEEN FINALISED.
- A MINIMUM 60% GROUND COVER MUST BE ACHIEVED ON ALL COMPLETED EARTHWORKS EXPOSED TO ACCELERATED SOIL EROSION WITHIN 30 DAYS DURING THOSE MONTHS WHEN THE EXPECTED RAINFALL IS LESS THAN 30mm; MINIMUM 70% COVER WITHIN 30 DAYS IF BETWEEN 30 AND 45mm; MINIMUM 70% COVER WITHIN 20 DAYS IF BETWEEN 45 AND 100mm; MINIMUM 75% COVER WITHIN 10 DAYS IF BETWEEN 100 AND 225mm; AND MINIMUM 80% COVER WITHIN 5 DAYS IF GREATER THAN 225mm. (ALTERNATIVE TO ABOVE)
- NO COMPLETED EARTHWORK SURFACE MUST REMAIN DENUDED FOR LONGER THAN 60 DAYS.
- THE TYPE OF GROUND COVER APPLIED TO COMPLETED EARTHWORKS IS COMPATIBLE WITH THE ANTICIPATED LONG-TERM LAND USE, ENVIRONMENTAL RISK, AND SITE REHABILITATION MEASURES.
- UNLESS OTHERWISE DIRECTED BY THE SUPERINTENDENT OR WHERE DIRECTED BY THE APPROVED REVEGETATION PLAN, TOPSOIL MUST BE PLACED AT A MINIMUM DEPTH OF 75mm ON SLOPES 4:1 (H:V) OR FLATTER, AND 50mm ON SLOPES STEEPER THAN 4:1.
- SOIL AMELIORANTS MUST BE ADDED TO THE SOIL IN ACCORDANCE WITH THE APPROVED LANDSCAPE/REVEGETATION PLANS AND/OR SOIL ANALYSIS.
- TEMPORARY SITE STABILISATION PROCEDURES MUST COMMENCE AT LEAST 30 DAYS PRIOR TO THE NOMINATED SITE SHUTDOWN DATE. AT LEAST 70% STABLE COVER OF ALL UNSTABLE AND/OR DISTURBED SOIL SURFACES MUST BE ACHIEVED PRIOR TO ANY SHUTDOWN. THE STABILISATION WORKS MUST NOT RELY UPON THE LONGEVITY OF NON-VEGETATED EROSION CONTROL BLANKETS, OR TEMPORARY SOIL BINDERS.
- ALL UNSTABLE OR DISTURBED SOIL SURFACES MUST BE ADEQUATELY STABILISED AGAINST EROSION (MINIMUM 70%) PRIOR TO COMMENCEMENT OF USE, OR SURVEY PLAN ENDORSEMENT.

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval: AP2023/005**

		SURVEY DATA		MATT HAACK – HAACK LOGISTICS GROUP		P0 Box 554 Beaudesert QLD 4285		ACS Engineers CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT					
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		EROSION AND SEDIMENT CONTROL – NOTES							
		MAP GRID											
		HEIGHT ORIGIN		HAACK – SANDY CREEK ROAD									
		SURVEY BOOKS											
3	INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	MA	02/2023	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285	13697	CIVIL	S. SHAY		21/12/23	ACS-230008-GEN-13	3
2	FOR APPROVAL	MS	23/06/2023										
1	PRELIMINARY	MA	19/04/2023										
REVISION/DETAILS		DWN	DATE	DES	DATE								
FILE: C:\1205\DATA\ACSS\YN\230008 HAACK - SANDY CREEK ROAD_015\DESIGN\DRAWING FILES\ACS-230008-GEN.DWG PLOT TIME: 21/12/2023 - 12:18PM BY USER: NICHOLAS FALVEY													



**SITE MANAGEMENT:**

1. ALL OFFICE FACILITIES AND OPERATIONAL ACTIVITIES MUST BE LOCATED SUCH THAT ANY LIQUID EFFLUENT (E.G. PROCESS WATER, WASH-DOWN WATER, EFFLUENT FROM EQUIPMENT CLEANING, OR PLANT WATERING), CAN BE TOTALLY CONTAINED AND TREATED WITHIN THE SITE.
2. THE CONSTRUCTION SCHEDULE MUST AIM TO MINIMISE THE DURATION THAT ANY AND ALL AREAS OF SOIL ARE EXPOSED TO THE EROSION EFFECTS OF WIND, RAIN AND SURFACE WATER.
3. LAND-DISTURBING ACTIVITIES MUST BE UNDERTAKEN IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN (ESCP) AND ASSOCIATED DEVELOPMENT CONDITIONS.
4. LAND-DISTURBING ACTIVITIES MUST BE UNDERTAKEN IN SUCH A MANNER THAT ALLOWS ALL REASONABLE AND PRACTICABLE MEASURES TO BE UNDERTAKEN TO:
  - (i) ALLOW STORMWATER TO PASS THROUGH THE SITE IN A CONTROLLED MANNER AND AT NON-EROSIVE FLOW VELOCITIES UP TO THE SPECIFIED DESIGN STORM DISCHARGE;
  - (ii) MINIMISE SOIL EROSION RESULTING FROM RAIN, WATER FLOW AND/OR WIND;
  - (iii) MINIMISE ADVERSE EFFECTS OF SEDIMENT RUNOFF, INCLUDING SAFETY ISSUES;
  - (iv) PREVENT OR AT LEAST MINIMISE, ENVIRONMENTAL HARM RESULTING FROM WORK-RELATED SOIL EROSION AND SEDIMENT RUNOFF;
  - (v) ENSURE THAT THE VALUE AND USE OF LAND/PROPERTIES ADJACENT TO THE DEVELOPMENT (INCLUDING ROADS) ARE NOT DIMINISHED AS A RESULT OF THE ADOPTED ESC MEASURES.
5. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST CONFORM TO THE STANDARDS AND SPECIFICATIONS CONTAINED IN:
  - (i) THE DEVELOPMENT APPROVAL CONDITION ISSUED BY RELEVANT AUTHORITY; AND/OR
  - (ii) THE APPROVED ESCP AND SUPPORTING DOCUMENTATION; OR
  - (iii) THE LATEST VERSION OF IECA (2008) BEST PRACTICE EROSION & SEDIMENT CONTROL IF THE STANDARDS AND SPECIFICATIONS ARE NOT CONTAINED IN THE APPROVED ESCP.
6. ANY WORKS THAT MAY CAUSE SIGNIFICANT SOIL DISTURBANCE AND ARE ANCILLARY TO ANY ACTIVITY FOR WHICH REGULATORY BODY APPROVAL IS REQUIRED, MUST NOT COMMENCE BEFORE THE ISSUE OF THAT APPROVAL.
7. ADDITIONAL AND/OR ALTERNATIVE ESC MEASURES MUST BE IMPLEMENTED IN THE EVENT THAT THE RELEVANT AUTHORITY IDENTIFIES THAT UNACCEPTABLE OFF-SITE SEDIMENTATION IS OCCURRING AS A RESULT OF THE WORK ACTIVITIES.
8. LAND-DISTURBING ACTIVITIES MUST NOT CAUSE UNNECESSARY SOIL DISTURBANCE IF AN ALTERNATIVE CONSTRUCTION PROCESS IS AVAILABLE THAT ACHIEVES THE SAME OR EQUIVALENT OUTCOMES AT AN EQUIVALENT COST.
9. SEDIMENT (INCLUDING CLAY, SILT, SAND, GRAVEL, SOIL, MUD, CEMENT AND CERAMIC WASTE) DEPOSITED OFF THE SITE AS A DIRECT RESULT OF AN ON-SITE ACTIVITY, MUST BE COLLECTED AND THE AREA APPROPRIATELY CLEANED/REHABILITATED AS SOON AS REASONABLE AND PRACTICABLE, AND IN A MANNER THAT GIVES APPROPRIATE CONSIDERATION TO THE SAFETY AND ENVIRONMENTAL RISKS ASSOCIATED WITH THE SEDIMENT DEPOSITION.
10. ALL WASTE INCLUDING PETROLEUM AND OIL-BASED PRODUCTS, MUST BE PREVENTED FROM ENTERING AN INTERNAL WATER BODY, OR AN EXTERNAL DRAIN, STORMWATER SYSTEM, OR WATER BODY.
11. ALL FLAMMABLE AND COMBUSTIBLE LIQUIDS, INCLUDING ALL LIQUID CHEMICALS IF SUCH CHEMICALS COULD POTENTIALLY BE WASHED OR DISCHARGED FROM THE SITE, ARE STORED AND HANDLED ON-SITE IN ACCORDANCE WITH RELEVANT STANDARDS SUCH AS AS1940 THE STORAGE AND HANDLING OF FLAMMABLE AND COMBUSTIBLE LIQUIDS.
12. NO MORE THAN 150m OF A STORMWATER, SEWER LINE OR OTHER SERVICE TRENCH MUST TO BE OPEN AT ANY ONE TIME.
13. SITE SPOIL MUST BE LAWFULLY DISPOSED OF IN A MANNER THAT DOES NOT RESULT IN ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.
14. ALL FILL MATERIAL PLACED ON SITE MUST COMPRISE ONLY NATURAL EARTH AND ROCK, AND IS TO BE FREE OF CONTAMINANTS, BE FREE DRAINING, AND BE COMPACTED IN LAYERS NOT EXCEEDING 300mm TO 90% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS1289.




**SITE MAINTENANCE:**

1. ENSURE ESC PLANS ARE ON SITE AT ALL TIMES.
2. ALL EROSION AND SEDIMENT CONTROL MEASURES, INCLUDING DRAINAGE CONTROL MEASURES, MUST BE MAINTAINED IN PROPER WORKING ORDER AT ALL TIMES DURING THEIR OPERATIONAL LIVES.
3. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES, INCLUDING DRAINAGE CONTROL MEASURES, MUST BE FULLY OPERATIONAL AND MAINTAINED IN PROPER WORKING ORDER AT ALL TIMES DURING THE MAINTENANCE PERIOD AS SPECIFIED BY RELEVANT AUTHORITY.
4. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES, INCLUDING DRAINAGE CONTROL MEASURES, MUST BE REMOVED AFTER ACHIEVING A SATISFACTORY "OFF-MAINTENANCE INSPECTION" BY THE RELEVANT AUTHORITY.
5. ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSPECTED:
  - (i) AT LEAST DAILY (WHEN WORK IS OCCURRING ON-SITE);
  - (ii) AT LEAST WEEKLY (WHEN WORK IS NOT OCCURRING ON-SITE);
  - (iii) WITHIN 24 HOURS OF EXPECTED RAINFALL; AND
  - (iv) WITHIN 18 HOURS OF A RAINFALL EVENT OF SUFFICIENT INTENSITY AND DURATION TO CAUSE RUNOFF ON-SITE).
 IF FAILURE HAS BEEN FOUND, IMMEDIATE REMEDIATIONS ARE REQUIRED AND TO A STANDARD WHICH ENSURES THE FAILURE DOES NOT CONTINUALLY OCCUR UNDER DESIGN RAINFALL CONDITIONS.
6. WASHING/FLUSHING OF SEALED ROADWAYS MUST ONLY OCCUR WHERE SWEEPING HAS FAILED TO REMOVE SUFFICIENT SEDIMENT AND THERE IS A COMPELLING NEED TO REMOVE THE REMAINING SEDIMENT (E.G. FOR SAFETY REASONS). IN SUCH CIRCUMSTANCES, ALL REASONABLE AND PRACTICABLE SEDIMENT CONTROL MEASURES MUST BE USED TO PREVENT, OR AT LEAST MINIMISE, THE RELEASE OF SEDIMENT INTO RECEIVING WATERS. ONLY THOSE MEASURES THAT WILL NOT CAUSE SAFETY AND PROPERTY FLOODING ISSUES SHALL BE EMPLOYED. SEDIMENT REMOVED FROM ROADWAYS MUST BE DISPOSED OF IN A LAWFUL MANNER THAT DOES NOT CAUSE ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.
7. SEDIMENT REMOVED FROM SEDIMENT TRAPS AND PLACES OF SEDIMENT DEPOSITION MUST BE DISPOSED OF IN A LAWFUL MANNER THAT DOES NOT CAUSE ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.
8. MAINTENANCE IS TO OCCUR ON ALL EROSION AND SEDIMENT CONTROL MEASURES WHEN CAPACITY REDUCES BY 30%.
9. MAINTENANCE MOWING OF ALL ROAD SHOULDERS, TABLE DRAINS, BATTERS AND OTHER SURFACES LIKELY TO EXPERIENCE ACCELERATED SOIL EROSION MUST AIM TO LEAVE THE GRASS LENGTH NO SHORTER THAN 50mm WHERE REASONABLE AND PRACTICABLE.
10. MAINTENANCE MOWING MUST BE DONE IN A MANNER THAT WILL NOT DAMAGE THE PROFILE OF FORMED, SOFT EDGES, SUCH AS THE CREST OF EARTH EMBANKMENTS.
11. ENSURE RECORDS ARE KEPT OF DATES OF MAINTENANCE AND THE PERSONNEL RESPONSIBLE FOR UNDERTAKING THE MAINTENANCE.
12. IT IS THE CONTRACTORS RESPONSIBILITY TO ENSURE SOIL EROSION IS LIMITED AS MUCH AS POSSIBLE. THE TECHNIQUES USED IN THE DESIGN SHOULD NOT BE TAKEN AS THE MAXIMUM CONTROLS ALLOWABLE, AND THE CONTRACTOR MAY ADD CONTROLS AS NECESSARY TO LIMIT SOIL EROSION AND SEDIMENTATION.
13. MONITORING SHALL BE UNDERTAKEN BY A PERSON WITH EXPERIENCE IN EROSION AND SEDIMENT CONTROL MONITORING. MONITORING IS TO BE UNDERTAKEN IN A MANNER WHICH COMPLIES WITH IECA GUIDELINES 2008, CHAPTER 7. SITE INSPECTION.

PLANS AND DOCUMENTS referred to in the SDA APPROVAL



SDA approval: AP2023/005








**RECOMMENDED MAX. BERM SPACING**


LAND SLOPE	MAX. SPACING
<2%	30m
5%	25m
10%	15m
20%	8m

		SURVEY DATA		MATT HAACK - HAACK LOGISTICS GROUP		EROSION AND SEDIMENT CONTROL - DETAILS		P0 Box 554 Beaudesert QLD 4285		 CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT	
		DATUM		590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				DRAWING NUMBER			
		MAP GRID		HAACK - SANDY CREEK ROAD		ENGINEERING CERTIFICATION (RPEQ)		(07) 5541 3500 www.acsengineers.com.au		ACS-230008-GEN-14	
3	INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285		#	FIELD	NAME	SIGNATURE	DATE	3
2	FOR APPROVAL	MS	23/06/2023			13697	CIVIL	S. SHAY		21/12/23	
1	PRELIMINARY	MA	19/04/2023	MA	02/2023						
REVISION/DETAILS		DWN	DATE	DES	DATE						




**LEGEND**

-  GEO LOG (COIR LOG)
-  MULCH BUNDS
-  ROCK PAD
-  SEEDING
-  FLOW ARROW



**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**

SDA approval: AP2023/005




REVISION/DETAILS		DWN	DATE	DES	DATE
3	INCLUSION OF SHED LAYOUT PLAN	MLS	24/11/2023	MA	02/2023
2	FOR APPROVAL	MS	23/06/2023		
1	PRELIMINARY	MA	19/04/2023		

SURVEY DATA	
MATT HAACK - HAACK LOGISTICS GROUP	
590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285	
HAACK - SANDY CREEK ROAD	
590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285	


EROSION AND SEDIMENT CONTROL - PLAN			
ENGINEERING CERTIFICATION (RPEQ)			
#	FIELD	NAME	DATE
13697	CIVIL	S. SHAY	21/12/23

P.O. Box 554 Beaudesert QLD 4285 (07) 5541 3500 www.acsengineers.com.au		 CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT
DRAWING NUMBER	REVISION	
ACS-230008-GEN-15	3	





SETOUT POINTS		
POINT #	EASTING	NORTHING
1	3940.078	2398.294
2	3941.734	2370.172
3	3928.322	2354.372
4	3927.088	2354.243
5	3927.921	2346.286
6	3929.485	2346.450
7	3945.755	2334.480
8	3950.856	2309.027



LONGITUDINAL SECTION  
GR-PROPERTY ACCESS Ch 0.000 to Ch 22.147  
SCALES: HORIZONTAL 1:100 VERTICAL 1:100

PLANS AND DOCUMENTS referred to in the SDA APPROVAL



SDA approval: AP2023/005

REVISION/DETAILS		DATE		DATE		DATE		DATE		DATE		DATE		DATE																																																																																																																																	
A	FOR APPROVAL	MLS	07/09/2023	MA	02/2023																																																																																																																																										
<table border="1"> <tr> <td colspan="4">SURVEY DATA</td> <td colspan="4">MATT HAACK - HAACK LOGISTICS GROUP</td> <td colspan="4">590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285</td> <td colspan="4">SECONDARY PROPERTY ACCESS LAYOUT</td> </tr> <tr> <td colspan="4">DATUM</td> <td colspan="4">HAACK - SANDY CREEK ROAD</td> <td colspan="4">#</td> <td colspan="4">ENGINEERING CERTIFICATION (RPEQ)</td> </tr> <tr> <td colspan="4">MAP GRID</td> <td colspan="4">590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285</td> <td colspan="4">FIELD</td> <td colspan="4">NAME</td> </tr> <tr> <td colspan="4">HEIGHT ORIGIN</td> <td colspan="4">590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285</td> <td colspan="4">SIGNATURE</td> <td colspan="4">DATE</td> </tr> <tr> <td colspan="4">SURVEY BOOKS</td> <td colspan="4"></td> <td colspan="4">S. SHAY</td> <td colspan="4">21/12/23</td> </tr> <tr> <td colspan="4">A</td> <td colspan="4">FOR APPROVAL</td> <td colspan="4">13697</td> <td colspan="4">CIVIL</td> </tr> <tr> <td colspan="4">REVISION/DETAILS</td> <td colspan="4">DWN</td> <td colspan="4">DATE</td> <td colspan="4">DES</td> </tr> <tr> <td colspan="4">DATE</td> <td colspan="4">DATE</td> <td colspan="4">DATE</td> <td colspan="4">DATE</td> </tr> </table>																SURVEY DATA				MATT HAACK - HAACK LOGISTICS GROUP				590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				SECONDARY PROPERTY ACCESS LAYOUT				DATUM				HAACK - SANDY CREEK ROAD				#				ENGINEERING CERTIFICATION (RPEQ)				MAP GRID				590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				FIELD				NAME				HEIGHT ORIGIN				590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				SIGNATURE				DATE				SURVEY BOOKS								S. SHAY				21/12/23				A				FOR APPROVAL				13697				CIVIL				REVISION/DETAILS				DWN				DATE				DES				DATE				DATE				DATE				DATE			
SURVEY DATA				MATT HAACK - HAACK LOGISTICS GROUP				590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				SECONDARY PROPERTY ACCESS LAYOUT																																																																																																																																			
DATUM				HAACK - SANDY CREEK ROAD				#				ENGINEERING CERTIFICATION (RPEQ)																																																																																																																																			
MAP GRID				590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				FIELD				NAME																																																																																																																																			
HEIGHT ORIGIN				590 SANDY CREEK ROAD, JOSEPHVILLE QLD 4285				SIGNATURE				DATE																																																																																																																																			
SURVEY BOOKS								S. SHAY				21/12/23																																																																																																																																			
A				FOR APPROVAL				13697				CIVIL																																																																																																																																			
REVISION/DETAILS				DWN				DATE				DES																																																																																																																																			
DATE				DATE				DATE				DATE																																																																																																																																			
P0 Box 554 Beaudesert QLD 4285 (07) 5541 3500 www.acsengineers.com.au												<b>ACS Engineers</b> CIVIL   ENVIRONMENTAL   PROJECT MANAGEMENT																																																																																																																																			
DRAWING NUMBER												REVISION																																																																																																																																			
ACS-230008-GEN-17												A																																																																																																																																			



# ACS Engineers

CIVIL | ENVIRONMENTAL | PROJECT MANAGEMENT

## Stormwater Management Plan



**Project Name: Dwelling House,  
Farm Sheds, Stables, Transport  
Depot and Caretaker Residence**

**Prepared for: M J Haack Pty Ltd**

590 Sandy Creek Road,  
JOSEPHVILLE QLD 4285

L1 RP32191

**PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL**



**SDA approval: AP2023/005**


ACS Engineers

18 January 2024

230008



Document Control:-

Rev No.	Author	Reviewed	Approved		Description	Date
	Name	Name	Name	Signature		
1	Malinda Sellars and Susan Shay	Susan Shay RPEQ 13697	Susan Shay RPEQ 13697		Draft for pre lodgement	
2	Malinda Sellars and Susan Shay	Susan Shay RPEQ 13697	Susan Shay RPEQ 13697		Updated following prelodgement	23.06.2023
3	Malinda Sellars and Susan Shay	Susan Shay RPEQ 13697	Susan Shay RPEQ 13697		RFI Update	18.01.2024

Digitally signed  
by Susan Shay  
RPEQ 13697  
Date:  
2024.01.18  
13:47:00 +10'00'

**Notes:**

- Revision 1 Draft
- Revision 2 Updated following prelodgement review. Seqwater codes added.
- Revision 3 Updated in response to Referral Entity Information Request

**Disclaimer:**

1. ACS Engineers (Aust) Pty Ltd has taken all reasonable steps to ensure that the information contained in this publication is accurate at the time of production. In some cases, ACS Engineers (Aust) Pty Ltd has relied on information supplied by the client(s).
2. This publication has been prepared in accordance with good professional practice. No other warranty, expressed or implied, is made as to the professional advice given in this publication.
3. ACS Engineers (Aust) Pty Ltd maintains **NO** responsibility for the misrepresentation of results due to incorrect use of information contained within this publication
4. This publication should remain together and be read as a whole.
5. This publication has been prepared solely for the benefit of the client listed above. No liability is accepted by ACS Engineers (Aust) Pty Ltd with respect to the use of publication by third parties without prior written approval.

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



SDA approval: AP2023/005



**Contents**

1. Introduction ..... 3

2. Site Details / Description of Development ..... 3

3. Stormwater Quantity ..... 4

    3.1. Catchment Description ..... 4

    3.2. Runoff Modelling ..... 5

        3.2.1. Methodology ..... 5

        3.2.2. Inputs ..... 6

        3.2.3. Analysis Results ..... 6

4. Stormwater Management ..... 7

5. Stormwater Quality ..... 7

    5.1. Potential Impacts ..... 7

    5.2. Proposed Stormwater Quality Management ..... 7

    5.3. Compliance ..... 8

6. Erosion and Sediment Control ..... 8

    6.1. Construction Phase ..... 10

    6.2. Operation Phase ..... 10

    6.3. Maintenance of Controls ..... 11

7. Conclusion ..... 13

Appendix A) Drawing List ..... 14

Appendix B) Seqwater Development Guidelines Assessment Benchmarks for Assessable Development – Performance Outcomes ..... 15

Appendix C) Effluent Disposal Report ..... 32

Appendix D) LURT Output ..... 33

Appendix E) Rational Method Calculations ..... 34

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**



**SDA approval: AP2023/005**



## 1. Introduction

This site-based stormwater management plan has been developed to identify the potential stormwater related impacts from the proposed development of 590 Sandy Creek Road, Josephville QLD 4285 at L1 RP32191.

The following report details the stormwater management requirements for the development in order to achieve compliance with the *Scenic Rim Regional Council Planning Scheme, Seqwater Development Guidelines for Water Quality Management in Drinking Water Catchments* and the *Environmental Protection (Water and Wetland Biodiversity) Policy 2019*, specifically the necessary mitigation measures to ensure that there is:

- no worsening of the stormwater discharges from the site into downstream properties,
- no worsening of flood plain extents; and
- no increased risk of contamination of downstream surface waters.

## 2. Site Details / Description of Development

The subject land comprises of one allotment: Lot 1 RP32191 (38.1 ha). The property is located approximately 8.8km south-west of the township of Beaudesert and lies within the Scenic Rim Regional Council (SRRC) Local Government Area, but with land uses regulated as part of the BSDA. The subject lot is zoned within the Special Industry Precinct as well as the Transition Precinct of the BSDA, as shown below in Figure 1.

The site has its access via Sandy Creek Road, a local council controlled road, constructed to a bitumen standard.

The land is not burdened by any easements.

The proposed development includes the construction of:

- Dwelling House
- Farm/Machinery Shed
- Transport Depot
- Caretakers Accommodation
- Horse Stable
- Property Access

The overall layout of the proposed development is detailed in the drawing set ACS-230008-GEN.

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval:** AP2023/005






Figure 1: BSDA Precinct Map (BSDA Development Scheme, 2017)

### 3. Stormwater Quantity

The proposed development including a dwelling house, farm shed and stable will contribute to an increase in the overall impervious area of the site. The extent of this increase and the proposed mitigation measures to ensure no worsening of the stormwater discharges from the site into downstream properties, and no worsening of flood plain extents is detailed in the subsequent sections.

#### 3.1. Catchment Description

For the purpose of the site-based stormwater management plan, the defined catchment is limited to the external boundaries of the development site. The development site falls generally to the west to Sandy Creek flood plain, as seen in Figure 2.



The site is surrounded by rural properties all zoned within the Special Industry Precinct under the BSDA. The subject lot is partially developed with cropping area and three (3) existing dams.



Figure 2: Subject Site Features (Source: QLD Globe)

The catchment has good grass cover, interspersed with trees. A slow soil permeability has been assumed for the stormwater runoff calculations due to the soil characteristics identified for the site, which are described as predominantly hard pedal red duplex soils.

### 3.2. Runoff Modelling

Runoff estimates have been calculated using the rational method and the project model which includes the property surface sourced from LiDAR data. The following results are to be read in conjunction with the project drawing set ACS-230008-GEN.

#### 3.2.1. Methodology

The rational method has been used to determine the peak runoff volumes generated from the site both pre and post development. The rainfall data for the site has been sourced from the Bureau of Meteorology design rainfall data system (2016). Slopes, stream lengths, sheet flow lengths and other characteristics have all been derived from the project model, created in Civil 3D.

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**



SDA approval: AP2023/005



### 3.2.2. Inputs

The following catchment data is required to calculate the expected peak flows:

- Catchment area and stream lengths
- Catchment fraction of impervious area
- Time of Concentration (TOC)
- IFD Data

Table 1 below details the catchment information in the pre- and post-development peak flow calculations. Time of concentration values were calculated in accordance with Friend's equation.

Table 1. Catchment Characteristics

Scenario	Catchment Area	Fraction Impervious	Time of Concentration
Pre Development	38 ha	0%	22 minutes
Post Development	38 ha	2%	22 minutes

### 3.2.3. Analysis Results

Table 2 below details the pre- and post-developed peak discharge rates and volumes from the site using the Rational Method.

Table 2. Peak Discharge Rates

Scenario	Peak Discharge 1% AEP	Volume 1% AEP
Pre Development	12.2 m <sup>3</sup> /s	13,407 m <sup>3</sup>
Post Development	12.2 m <sup>3</sup> /s	13,558 m <sup>3</sup>

The increase in impervious area (hardstand and sheds) does not result in a shortening of the time of concentration due to the catchment characteristics and therefore there is not expected to be a change in the peak flow discharging the site as a result of the proposed development. The runoff will be managed through a new grassed swale and the existing farm dams which will be used for on site irrigation and stock water needs. Roofwater will be captured in two 100kL rainwater tanks for potable and landscaping uses. Overflows from the tanks will be directed to the grassed swale drain.

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**



SDA approval: AP2023/005



## 4. Stormwater Management

Stormwater on site and discharging from the site will be managed in accordance with this report and project drawing ACS-230008-GEN-09.

While there is not expected to be an increase in peak discharge post-development, the following stormwater quantity management controls have been proposed:

- Overland flow directed into swale drains;
- Roof water directed to rainwater tanks through stormwater pipes with overflow to discharge to swale drain;
- Swale drains directed to water supply dams each with dual bywashes. Dam outflows to occur as overland sheet flow via the bywashes and directed to natural drainage paths.

## 5. Stormwater Quality

### 5.1. Potential Impacts

On-site operations have the potential to impact on surface runoff water quality if inadequately managed. These activities may include:

- Initial construction phase development (e.g. groundcover/topsoil stripping, road and hardstand construction)
- Increased oils, greases, fuels, and other chemicals due to increased traffic activity
- Spillage during handling and transport of materials
- Effluent disposal

Urbanisation has the potential to increase the quantity of stormwater pollutants that are discharged to receiving waters. This can have a detrimental effect on those receiving environments and potentially impact the natural water cycle, ecological health and drinking water supplies.

### 5.2. Proposed Stormwater Quality Management

The potential impacts of on-site operations for the subject site prompt the requirement of a stormwater quality treatment train. The treatment train consists of the following:

1. Stormwater runoff from roof to be directed into rainwater tanks
2. Tank overflows and carparking areas directed to grassed swale drains;
3. Undercover washdown areas will incorporate Fox Diversion (or approved similar) systems with silt baskets, holding tanks, oil/water separator and pump out tanks
4. Grassed swale drains to be directed to detention basins/water supply dams.
5. Captured water in rainwater tanks and detention basins/water supply dams to be reused on site for potable and irrigation uses.

The stormwater quality treatment train is shown on drawing ACS-230008-GEN-09.

Effluent disposal from the proposed dwelling, caretakers residence and transport depot amenities will be undertaken in accordance with the Site and Soil Evaluation (Stavs Hydraulic Services, Jan 2024). Refer to Appendix C).



### 5.3. Compliance

The established controls have been assessed to ensure the achievement of reductions in mean annual nutrient loads from an unmitigated development.

The existing and developed drainage path characteristics, along with source contaminant characteristics, were modelled using the MUSIC software in accordance with MUSIC Modelling Guidelines (Water By Design, 2018). The reduction targets are outlined in Table 3 below along with the modelled train effectiveness, demonstrating compliance with the reduction targets. The MUSIC Modelling Report can be provided upon request for model input and results information.

Table 3. Nutrient Removal Targets and Model Results

Nutrient Parameter	Reductions in mean annual load from unmitigated development (Seqwater Development Guidelines)	Modelled Treatment Train Effectiveness
<b>Total Suspended Solids (kg/yr)</b>	85% Reduction	98.9%
<b>Total Phosphorous (kg/yr)</b>	65% Reduction	97.5%
<b>Total Nitrogen (kg/yr)</b>	45% Reduction	96.8%
<b>Gross Pollutants (kg/yr)</b>	95% Reduction	100%

If best practice management is followed, along with the proposed stormwater quality management controls, the quality of the stormwater discharging from the site is expected to remain at or below pre-development quality. Runoff from all disturbed areas of the site will be directed to the water supply/detention basin for sediment capture and nutrient removal.

The development will also achieve the requirements of the *Seqwater Development Guidelines for Water Quality Management in Drinking Water Catchments*. Refer to Appendix B) and Appendix D).

## 6. Erosion and Sediment Control

Sediment will be generated as a result of the development works. While the potential exists for sediment to be generated during the construction phase, the potential sediment volume is dependent upon rainfall, site topography, the material type exposed, flow characteristics, and the construction practices and program.

The potential sediment yield during construction will vary with the extent of site exposed during the construction programme. It is recommended that the following measures be adopted along with the whole of site and construction stag specific sediment and erosion control plans detailed on drawings ACS-230008-GEN-09 to 12 to ensure that the water quality of the receiving waters is not adversely impacted by the development works.

Potential erosion and sediment generation and risk assessment is undertaken using the Revised Universal Soil Loss Equation (RUSLE).

RUSLE calculates annual erosion rates based on:

$$A = R \times K \times LS \times C \times P$$

Where:

- A = annual soil loss due to erosion (t/ha/yr)
- R = rainfall erosivity factor
- K = soil erodibility factor
- LS = topographic factor derived from slope length and gradient
- C = cover and management factor
- P = erosion control practice factor

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**



**SDA approval:** AP2023/005



Table 3 below shows the factors used for the erosion risk assessment.

Table 3. RUSLE Factors Used for Assessment


Factor	Reference	Value
<b>R</b>	Calculated from Table E1 from the IECA Best Practice Erosion and Sediment Control, Book 2, Appendix E.	2177
<b>K</b>	Table E4 from the IECA Best Practice Erosion and Sediment Control, Book 2, Appendix E.	0.025
<b>LS</b>	Table E3 from the IECA Best Practice Erosion and Sediment Control, Book 2, Appendix E.	2.81
<b>C</b>	Table E9 from the IECA Best Practice Erosion and Sediment Control, Book 2, Appendix E.	1
<b>P</b>	Table E11 from the IECA Best Practice Erosion and Sediment Control, Book 2, Appendix E.	1.3

Figure 3 and Figure 4 below show the calculated annual soil loss and associated risk assessment, varied by the LS factor.

Slope Ratio	Slope Gradient (%)	Slope Length (m)							
		10	20	30	40	50	60	70	80
1 in 100	1	8	9	11	11	12	13	13	13
1 in 50	2	13	17	20	22	24	25	28	29
1 in 33	3	17	24	29	33	37	40	43	46
1 in 25	4	21	31	38	45	50	55	60	64
1 in 20	5	25	38	48	57	64	71	78	84
1 in 16.6	6	30	45	57	69	79	88	96	104
1 in 12.5	8	37	57	76	93	107	120	119	145
1 in 10	10	48	77	102	124	144	163	181	199
1 in 8.3	12	60	98	131	161	188	214	238	262
1 in 7.1	14	72	120	160	197	232	265	296	326
1 in 6.3	16	84	140	189	234	276	316	354	391
1 in 5.5	18	96	161	217	270	319	366	411	454
1 in 5	20	106	180	245	306	362	416	468	518
1 in 4	25	133	229	313	392	466	538	606	673
1 in 3.3	30	158	273	376	473	565	653	738	821
1 in 2.5	40	200	352	490	618	741	860	974	1132
1 in 2	50	236	417	582	737	886	1029	1061	1415

Figure 3 - Annual Soil Loss and Erosion Risk Ratings for Various Slopes

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval:** AP2023/005



Soil Loss Class	Soil Loss Rate (t/ha/yr)	Soil Erosion Risk Rating
1	0 to 150	Very Low
2	151 to 225	Low
3	226 to 350	Low-moderate
4	351 to 500	Moderate
5 to 6	501 to 1500	High
7	above 1500	Extremely High

Figure 4 - Erosion Risk Rating Definitions

Table 4 - Annual Soil Loss Estimate and Control Type Recommended

Result	Rate	Value
A	t/ha/yr	199
A	t/yr	149
Control		Type 2

The subject site has a very low soil erosion risk rating. However erosion and sediment controls are required to mitigate against any potential risks.

Erosion and sediment control measures are to be adopted in accordance with IECA Best Practice Erosion and Sediment Control, and drawings ACS-230008-GEN-09 to 12, and the measures are outlined below.

### 6.1. Construction Phase

- a) Construct stabilised shake down area at the site access.
- b) Construct diversion drains and direct to existing detention basin as detailed on the engineering plans.
- c) Erect sediment controls including mulch bunds as detailed on the engineering plans.
- d) Strip topsoil and stockpile within the controlled area on site.
- e) Carry out bulk earthworks involving cut to fill.
- f) Exposed soils and stockpiles are to be watered, as required, to minimise soil losses as a result of wind.
- g) Finalised earthworks to be top soiled and seeded or landscaped as directed.
- h) Maintain all sediment devices and other interim controls regularly.
- i) Remove sediment controls after the establishment of the landscaping and grass cover.

### 6.2. Operation Phase

- a) Drains to be turfed, or grass seeded with turf reinforcing matting overlain. Water collected within the detention basins may be used for watering grass seed.
- a) Basin in/outflow areas to be lined with geotextile, overlain by 50 mm rock and allowed to grass over for velocity and scour control.
- b) All embankments post construction to be turfed, grass seeded, or stabilised with plants and heavy mulching.

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005



### 6.3. Maintenance of Controls

Type of Maintenance Control	Measures
<b>General</b>	<p>These notes must be read in conjunction with the erosion and sediment control site plan and associated notes. Should there be a discrepancy in notes between documents, this document takes precedence.</p> <p>The Owner is responsible for the installation and maintenance of the sediment and erosion control measures during the construction phase. In the event that site conditions change considerably from those considered within this management plan, a revised erosion and sediment control plan must be designed and implemented.</p> <p>All erosion and sediment control measures, including drainage control, must be maintained in proper working order at all times during their operational lives.</p> <p>Sediment removed from sediment traps and places of sediment deposition must be disposed of in a lawful manner that does not cause ongoing soil erosion or environmental harm.</p>
<b>Land Clearing</b>	<p>Land clearing should not occur unless preceded by the installation of all necessary drainage and sediment control structures. The exemption would be any land clearing necessary to allow installation of these control measures.</p> <p>Land clearing is to be staged according to the relevant staging plans. If vegetation clearing must be carried out well in advance of earthworks, this clearing should be limited to the removal of woody vegetation only. Clearing and grubbing and removal of existing ground cover should not occur until immediately prior to earthworks occurring in that stage of works.</p>
<b>Construction Staging</b>	<p>Where possible, the bulk of the earth works should occur when rainfall totals are typically at the lowest for the year.</p> <p>Construction staging to occur in accordance with the approved construction staging plans.</p> <p>All new erosion and sediment controls are to be constructed, and existing controls cleaned, prior to the construction of the next stage of the project.</p>
<b>Site Access</b>	<p>Site entry/exit points shall be appropriately managed to minimize the risk of sediment being tracked onto sealed, public roadways.</p>
<b>Soil Stockpiling</b>	<p>If any soils are to be stockpiled on site, stockpiles must be: Appropriately protected from wind, concentrated surface flow and excessive up-slope stormwater surface flows. Located at least 2 m away from any hazardous area, retained vegetation, or drainage area. Located up-slope of an appropriate sediment control system (correctly installed sediment fence). Provided with an appropriate protective cover (synthetic, mulch or vegetative) if soil is to be stockpiled for more than 28 days.</p>
<b>Site Monitoring</b>	<p>Erosion and sediment control measures to be inspected daily by the site manager (or nominated representative) during periods of runoff-producing rainfall, and de-silted, repaired and amended as appropriate.</p> <p><b>Daily site inspections</b>, during periods of runoff-producing rainfall must include:</p> <ul style="list-style-type: none"> <li>• all drainage, erosion and sediment control measures;</li> <li>• occurrences of excessive sediment deposition (whether on-site or off-site);</li> <li>• all site discharge points.</li> </ul> <p>Weekly site inspections must include:</p> <ul style="list-style-type: none"> <li>• all drainage, erosion and sediment control measures;</li> <li>• occurrences of excessive sediment deposition (whether on-site or off-site);</li> </ul>



Type of Maintenance Control	Measures
	<ul style="list-style-type: none"> <li>• occurrences of construction materials, litter or sediment placed, deposited, washed or blown from the site, including deposition by vehicular movements;</li> <li>• litter and waste receptors;</li> <li>• oil, fuel and chemical storage facilities.</li> </ul> <p>Site inspections immediately prior to anticipated runoff-producing rainfall must include:</p> <ul style="list-style-type: none"> <li>• all drainage, erosion and sediment control measures</li> </ul> <p>Site inspections immediately <b>following runoff-producing rainfall</b> must include:</p> <ul style="list-style-type: none"> <li>• treatment and de-watering requirements of sediment basins;</li> <li>• sediment deposition within sediment basins and the need for its removal;</li> <li>• all drainage, erosion and sediment control measures;</li> <li>• occurrences of excessive sediment deposition (whether on-site or off-site);</li> <li>• occurrences of construction materials, litter or sediment placed, deposited, washed or blown from the site, including deposition by vehicular movements;</li> <li>• occurrences of excessive erosion, sedimentation, or mud generation around the site office, car park and material storage areas.</li> </ul> <p>In addition to the above, <b>monthly site inspections</b> must include:</p> <ul style="list-style-type: none"> <li>• surface coverage of finished surfaces (both area and percentage cover);</li> <li>• health of recently established vegetation;</li> <li>• proposed staging of future site clearing, earthworks and site/soil stabilisation.</li> </ul>
<p><b>Drainage Control Management</b></p>	<p>Inspect all drainage lines for erosion around the edges of the drain prior to forecast rainfall, and after significant runoff producing storm events, and repair if required.</p> <p>Check for movement of, or damage to, the drain and immediately repair as necessary.</p> <p>During construction, all reasonable and practicable measures must be implemented to control flow velocities in such a manner that prevents soil erosion along drainage paths and at the entrance/exit point of all drains and drainage structures.</p> <p>All temporary earth banks, flow diversion systems, and sediment basin embankments must be machine compacted, seeded and mulched within 10 days of formation for the purpose of establishing a vegetative cover, unless otherwise stated in an approved Vegetation Management Plan.</p> <p>Remove all sediment from the drains prior to and after rainfall events to ensure the sediment pond capacity is maintained.</p>
<p><b>Sediment Control Management</b></p>	<p>Inspect coarse sediment traps prior to forecast rain events and after runoff producing storm events. All necessary repairs are to be made immediately. When making repairs, restore the system to the original configuration, unless an amended layout is required or specified.</p> <p>If the fabric is sagging at any point, install additional support posts/stakes.</p> <p>Remove any accumulated sediment in sediment traps or catch drains if the sediment deposit exceeds a depth of 100 mm.</p> <p>All detention basins are to be inspected after each runoff event. If damage has occurred at inlet and outlet weir locations, make the necessary repairs. Clean out accumulated sediment once basin storage has been decreased by 20%.</p> <p>Water within the detention basin is to be reused on site only, and can be used for dust suppression and vegetation watering.</p> <p>Reuse of water from the detention basins is to be undertaken in a manner which does not cause erosion in the applied area.</p>



Type of Maintenance Control	Measures
<b>Site Rehabilitation/Revegetation Management</b>	<p>Site revegetation must occur in accordance with the approved vegetation plan.</p> <p>A minimum 70% ground cover must be achieved on all non-completed earthworks if further construction activities or soil disturbances are likely to be suspended for more than 30 days.</p> <p>No completed earthworks surface shall remain denuded for longer than 60 days.</p> <p>All cut and fill earth batters must be topsoiled and grassed/seeded within 10 days of completion of grading.</p> <p>Maintenance responsibility for the establishment of vegetation, that is the requirement to irrigate the plants and grass used to generate ground cover, lies with the Owner.</p>
<b>Responses to Complaints</b>	<p>Complaints during this type of construction usually relate to noise and dust. Generally, the complaint is made known to the Contractor, the Principal, the Superintendent and/or the Council.</p> <p>The Contractor shall keep a record of all complaints identifying the nature of the complaint and any remedial action taken to address such complaint. The Contractor shall act as soon as possible to remedy the problem, if the complaint is considered valid and reasonable. A complaints record shall be made available by the contractor for regular inspection by the Superintendent. For the purpose of direction by others, the Contractor's details are to be supplied to Council prior to commencement of the works.</p> <p>Complaints relating to dust shall require the Contractor to immediately water the exposed earth surfaces and any soil stockpile areas as well as haul roads to control dust. Such watering shall occur immediately when the complaint is registered with the Contractor. Watering should continue periodically until conditions suit, or the works are completed to a state that prevents dust transport.</p>

## 7. Conclusion

This Stormwater Management Plan Report has demonstrated that the potential stormwater impacts associated with the proposed development are within acceptable and manageable limits. The development is unlikely to have any adverse impacts on neighboring properties and the surrounding environment, with respect to stormwater quantity and quality.

If best practice management is followed, along with the proposed stormwater quantity and quality management controls, the site will achieve compliance with the *Bromelton State Development Area Planning Scheme*, the *Scenic Rim Regional Council Planning Scheme*, the *Seqwater Development Guidelines for Water Quality Management in Drinking Water Catchments* and the *Environmental Protection (Water and Wetland Biodiversity) Policy 2019* and the likelihood of environmental harm will be low.

This report is to be read and implemented in conjunction with the stormwater management and general layout plans ACS-230008-GEN.

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval:** AP2023/005



**Appendix A) Drawing List**

Sheet Number	Sheet Title	Revision
01	Cover Sheet	3
02	General Notes	3
03	Staging Plan	3
04	Overall Site Layout Plan	3
05	Detailed Layout Plan – Stage 1	3
06	Detailed Layout Plan – Stage 2	3
07	Shed Layout Plan	3
08	Property Access Detail	3
09	Bulk Earthworks Plan – Stage 1	3
10	Sections	3
11	Landscape Plan	3
12	Stormwater Management Plan	3
13	Erosion and Sediment Control – Notes	3
14	Erosion and Sediment Control – Details	3
15	Erosion and Sediment Control – Plan	3
16	Surrounding Precincts Plan	3

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**



**SDA approval:** AP2023/005



## Appendix B) Seqwater Development Guidelines Assessment Benchmarks for Assessable Development – Performance Outcomes

Table 5: Assessment benchmarks for assessable development

Performance Outcomes	Acceptable Outcomes	Compliance
Separation distances		
<p>PO1</p> <p>Development maintains an adequate separation distance and avoids areas of potential flood inundation to protect waterways or water supply sources.</p>	<p>AO1.1</p> <p>Development complies with the separation distances and other locational criteria specified in Table 5.</p> <p><b>Note:</b> Where another setback distance or locational criteria is identified within this code, the higher standard applies.</p>	<p><b>Complies.</b> Proposed development is located more than 100m from the nearest waterway (stream order 5) and the 1%AEP flood extent. Refer to drawing set ACS-230008-GEN for details.</p>
Wastewater (other than domestic wastewater)		
<p>PO2</p> <p>Development does not discharge wastewater unless demonstrated to not compromise the drinking water supply environmental values.</p> <p><b>Note:</b> Drinking water supply environmental values are referenced within Schedule 1 of the <i>Environmental Protection Policy (Water) 2009</i>.</p>	<p>AO2.1</p> <p>Development does not generate wastewater.</p> <p>OR</p> <p>AO2.2</p> <p>If development generates wastewater, the wastewater is collected and contained on-site, and is:</p> <ol style="list-style-type: none"> <li>lawfully disposed to sewer;</li> <li>transferred off-site for treatment/disposal to an appropriately licensed facility;</li> </ol>	<p><b>Complies.</b> The proposed development does not release wastewater other than domestic wastewater. Any wastewater associated with the service area and truck wash down is captured and directed to treatment systems with wastewater stored in holding tanks for disposal off site by licenced contractors</p>

**PLANS AND DOCUMENTS referred to in the SDA APPROVAL**




**SDA approval: AP2023/005**



Performance Outcomes	Acceptable Outcomes	Compliance
	<p>c. reused on-site in a closed-cycle irrigation scheme, industrial processes, washing/cleaning or other purpose; or</p> <p>d. treated to meet the drinking water supply environmental values prior to release.</p> <p><b>Note:</b> Where development involves the release of wastewater, a Wastewater Management Plan (WWMP) is to be prepared by a suitably qualified person. Plans are to provide an assessment of all risks and associated mitigation strategies for preventing adverse impact on the quality of drinking water and may require a water quality monitoring program.</p>	
<p>PO3</p> <p>Where treated wastewater is irrigated to land, it will:</p> <ul style="list-style-type: none"> <li>a. be confined to a dedicated area of land on-site;</li> <li>b. be suitably located and sized; and</li> <li>c. use irrigation practices that will not harm groundwater and on-site surface water quality.</li> </ul> <p><b>Note:</b> Developments involving the irrigation of wastewater will need to provide a MEDLI Modelling Report demonstrating the nominated land area for wastewater irrigation is suitably located and sized to accommodate design wastewater loads, storages are suitably sized to accommodate design wastewater loads, and proposed irrigation</p>	<p>No acceptable outcome is nominated.</p>	<p><b>Complies.</b> The proposed development does not release wastewater other than domestic wastewater.</p>

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**




**SDA approval: AP2023/005**



Performance Outcomes	Acceptable Outcomes	Compliance
<p>practices will not damage water quality. It is recommended the modelling exercise incorporate scenarios based on both a 10-year and 20-year planning horizon.</p>		
<p>Solid Waste</p>		
<p>PO4</p> <p>Solid wastes generated by the development must be managed, stored and disposed in a manner that does not adversely impact on the quality of any surface water or groundwater.</p>	<p>The following acceptable outcomes are applicable to intensive animal industry only. For all other development, no acceptable outcome is nominated.</p> <p>AO4.1</p> <p>The stockpiling of waste litter, manure and other organics is undertaken as follows:</p> <ul style="list-style-type: none"> <li>a. on surfaces constructed with permanent impervious underlay to prevent leaching (groundsheets will only be accepted where stockpiling is temporary);</li> <li>b. located outside of an effluent irrigation area;</li> <li>c. located 3m above the seasonal high-water table and away from recharge areas;</li> <li>d. sized to accommodate the proposed disposal timeframes;</li> <li>e. designed with run-off diversion drainage upstream to prevent uncontaminated stormwater movement into the area;</li> </ul>	<p><b>Complies.</b> The proposed development is not an intensive animal industry. The proposed development site is located within SRRC's domestic waste collection zone. Any commercial waste/non-standard domestic waste is able to be transported by the residents/operators to Council's nearest waste disposal facility at Bromelton. The proposed development is not expected to generate any additional waste loads than those typical of a rural residential use or light industry.</p>

**PLANS AND DOCUMENTS referred to in the SDA APPROVAL**

**SDA approval: AP2023/005**






Performance Outcomes	Acceptable Outcomes	Compliance
	<p>f. bunded to capture contaminated run-off for appropriate treatment and disposal; and</p> <p>g. covered, desirably within a shed but otherwise with weatherproof material.</p> <p>AND</p> <p>AO4.2</p> <p>The reuse of waste litter, manure and other organics as soil conditioners or fertilizers is not undertaken on-site.</p> <p>AND</p> <p>AO4.3</p> <p>Composting activities are not undertaken on-site.</p> <p>AND</p> <p>AO4.4</p> <p>Carcasses are not buried on-site except as required in accordance with any emergency animal disease directive by a biosecurity agency.</p>	
Wastewater		
<p>PO5</p> <p>Wastewater treatment systems are designed, constructed and managed in ways that do not compromise the drinking water supply environmental values.</p>	<p>AO5.1</p> <p>Development does not involve an on-site wastewater facility.</p> <p>OR</p>	<p><b>Complies.</b> The on site wastewater treatment and effluent disposal system achieves a medium risk classification in accordance with Seqwater’s Land Use Risk Tool for on-site sewage facilities. Refer to Site and Soil Evaluation Report by Stav’s Hydraulic</p>



Performance Outcomes	Acceptable Outcomes	Compliance
<p><b>Note:</b> water supply environmental values are referenced within Schedule 1 of the Environmental Protection Policy (Water) 2009.</p>	<p>AO5.2</p> <p>Where the combined total peak design capacity of wastewater treatment is less than 21 Equivalent Persons (EP), the design of the system achieves a Low or Medium Risk classification in accordance with Seqwater's <i>Land Use Risk Tool for on-site sewage facilities</i>.</p> <p>OR</p> <p>AO5.3</p> <p>Where the combined total peak design capacity of wastewater treatment is 21EP or greater, the system is located and designed in the following manner:</p> <ol style="list-style-type: none"> <li>a. achieves a minimum secondary treatment standard with nutrient removal and disinfection;</li> <li>b. on land at or above the 0.5% AEP flood event;</li> <li>c. the hydraulic capacity of the system is five times the average dry weather flow (ADWF);</li> <li>d. no direct discharge of sewage to a waterway or water supply source occurs, unless during a bypass event that exceeds peak hydraulic capacity and sewage is screened and disinfected before release;</li> </ol>	<p>Services and LURT Output. The design capacity is less than 21 EP.</p>

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**




SDA approval: AP2023/005



Performance Outcomes	Acceptable Outcomes	Compliance
	<p>e. where treated effluent will be used in irrigation, application is:</p> <ul style="list-style-type: none"> <li>i. confined to a dedicated area of land suitably located and sized, and using irrigation practices that will not adversely affect groundwater and surface water quality; and</li> <li>ii. located on land at or above the 0.5% AEP flood event; and</li> </ul> <p>f. where the combined total peak design capacity of wastewater treatment is 1500EP or greater, and direct discharge to a waterway is the only reasonably practical disposal option, the contribution of flow from the system must be modelled over the range of reasonably expected flow events. If the proportion of flow is:</p> <ul style="list-style-type: none"> <li>i. &lt;10% of the total flow, 3-log reduction bacteria and virus, and 4-log reduction protozoa, minimum pathogen log-reduction values apply; or</li> <li>ii. &gt;10% of the total flow, it must demonstrate compliance with the Australian guidelines for water recycling (Phase 2): Augmentation of drinking</li> </ul>	

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**




SDA approval: AP2023/005



Performance Outcomes	Acceptable Outcomes	Compliance
	<p>water supply (to be undertaken in consultation with Seqwater).</p> <p><b>Note:</b> Developments involving the irrigation of wastewater will need to provide a MEDLI Modelling Report demonstrating the nominated land area for irrigation is suitably located and sized to accommodate design wastewater loads, storages are suitably sized to accommodate design wastewater loads and proposed irrigation practices will not result in any adverse impact on water quality. It is recommended the modelling exercise incorporate scenarios based on both a 10-year and 20-year planning horizon and incorporate a minimum of three irrigation concepts.</p>	
Vegetation management		
<p>PO6</p> <p>Maintain the current extent of any vegetation located adjacent, or connected, to any waterway or water supply source.</p>	<p>AO6.1</p> <p>Clearing complies with the following locational criteria:</p> <ul style="list-style-type: none"> <li>a. 25m setback to a stream order 1–3;</li> <li>b. 50m setback to a stream order 4 or greater;</li> <li>c. 200m setback to a full supply level of a dam, lake or reservoir or watercourse that serves as a potable water supply;</li> <li>d. is not undertaken on land within the 1% AEP flood event; and</li> </ul>	<p><b>Complies.</b> No clearing is proposed within the waterways or 50m setback of the waterways. The development is not undertaken within the 1% AEP flood extent and is not undertaken on land with a slope greater than 15%.</p>

**PLANS AND DOCUMENTS referred to in the SDA APPROVAL**




**SDA approval: AP2023/005**



Performance Outcomes	Acceptable Outcomes	Compliance
	e. is not undertaken on a slope greater than 15%.	
Stormwater quality and hydrology		
<p>PO7</p> <p>Manage stormwater at the construction phase to protect drinking water supply environmental values and facilitate the achievement of water quality objectives for receiving waters.</p> <p><b>Note:</b> Drinking water supply environmental values are referenced within Schedule 1 of the <i>Environmental Protection Policy (Water) 2009</i>.</p>	<p>A07.1</p> <p>At the construction stage, an erosion and sediment control program (ESCP) demonstrates that stormwater achieves the design objectives listed in Table A of the SPP (appendix 2): <i>Construction Phase – Stormwater management design objectives</i> (all parts).</p> <p>OR</p> <p>A07.2</p> <p>An ESCP demonstrates how stormwater quality will be managed at the construction stage in accordance with an acceptable regional or local guideline so that target contaminants are treated to a design objective at least equivalent to Table A of the SPP (all parts).</p> <p>OR</p> <p>A07.3</p> <p>Stormwater run-off generated during construction is captured and transferred off-site or captured and treated to any applicable re-use standards and reused on-site.</p>	<p><b>Complies.</b> A construction stage erosion and sediment control plans has been developed as part of this site based stormwater management plan. Refer to section 6 of this report and the proposal plans ACS-230008-GEN.</p>
PO8	A08.1	<b>Complies.</b> The proposed stormwater quality treatment train achieves the minimum reduction in

Performance Outcomes	Acceptable Outcomes	Compliance
<p>Manage stormwater during operational (postconstruction) stages to protect drinking water supply environmental values and facilitate the achievement of water quality objectives for receiving waters.</p> <p><b>Note:</b> Drinking water supply environmental values are referenced within Schedule 1 of the <i>Environmental Protection Policy (Water) 2009</i>.</p>	<p>Development does not involve an impervious area greater than 1,000m<sup>2</sup>.</p> <p>OR</p> <p>AO8.2</p> <p>Development is for reconfiguring a lot that;</p> <ul style="list-style-type: none"> <li>a. will not create more than two additional lots; or</li> <li>b. involves a land area less than 1,000m<sup>2</sup>.</li> </ul> <p>OR</p> <p>AO8.3</p> <p>Stormwater run-off generated during operation (post-construction) demonstrates a minimum reduction in mean annual load from unmitigated development that achieves the following stormwater management design objectives:</p> <ul style="list-style-type: none"> <li>• 85% reduction in total suspended solids;</li> <li>• 65% reduction in total phosphorus;</li> <li>• 45% reduction in total nitrogen; and</li> <li>• 95% reduction in gross pollutants.</li> </ul> <p>OR</p> <p>AO8.4</p>	<p>mean annual loads (AO8.3) from the unmitigated development. Refer to section 5 of this report.</p>

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**




**SDA approval: AP2023/005**



Performance Outcomes	Acceptable Outcomes	Compliance
	<p>Stormwater run-off generated during operation is captured and transferred off-site or captured and treated to any applicable re-use standards and reused on-site.</p> <p><b>Note:</b> A Site Stormwater Quality Management Plan is to be prepared by a suitably qualified individual such as a Civil Engineer or an Environmental Professional and is to be certified by a Registered Professional Engineer (RPEQ) (Civil or Environmental) to demonstrate compliance with the stormwater design objectives.</p>	
<p>PO9</p> <p>Development maintains or improves the quality of surface water by adopting measures that exclude livestock from entering a water body where a site is being used for animal husbandry or animal-keeping activities.</p>	No acceptable outcome is nominated.	<p><b>Complies.</b> The waterway is fenced from livestock. No livestock will have access to water bodies on the subject site except when crossing the creek via the existing farm track and bed level crossing, under controlled conditions, to access grazing areas on either side. Access to the creek will be limited to the time to move the herd from one side to the other (approx. 1 – 2 hours)</p>
<p>PO10</p> <p>Development avoids and minimises changes to the existing surface water natural hydrological regime so that:</p> <p>a. there is no change to the reference high-flow and low-flow duration frequency curves, low-flow spells frequency curve and mean annual flow to and from waterways as a result of the development;</p>	No acceptable outcome is nominated.	<p><b>Complies.</b> As demonstrated in this report there is not expected to be any change to existing surface water natural hydrological regimes as a result of the proposed development. Existing flows will be maintained.</p>


**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**



**SDA approval: AP2023/005**

Performance Outcomes	Acceptable Outcomes	Compliance
<ul style="list-style-type: none"> <li>b. any relevant flows into waterways comply with the relevant flow objectives of the applicable water plan for the area; and</li> <li>c. the collection and re-use of stormwater occurs so there is no increase to the velocity or volume of stormwater flows entering a waterway.</li> </ul>		
<p>PO11</p> <p>The design and location of artificial waterways:</p> <ul style="list-style-type: none"> <li>a. use natural channel design principles to minimise erosion, flooding and maintenance while maximising ecological and aesthetic values of waterways;</li> <li>b. are compatible with any existing natural waterways; and</li> <li>c. are designed to ensure surface water hydrological regimes are maintained.</li> </ul>	<p>No acceptable outcome is nominated.</p> <p><b>Note:</b> The Ipswich City Council Waterway and Channel Rehabilitation Guidelines or Brisbane City Council Natural Channel Design Guidelines demonstrate suitable natural channel design works.</p>	<p><b>N/A.</b> No artificial waterways are proposed.</p>
<p>PO12</p> <p>Development maintains the existing groundwater hydrological regime.</p>	<p>AO12.1</p> <p>Development does not change the existing groundwater hydrological regime by lowering or raising the water table and hydrostatic pressure outside the bounds of variability of existing predevelopment conditions.</p> <p>AND</p> <p>AO12.2</p>	<p><b>Complies.</b> The proposed development is not expected to change existing groundwater hydrological regimes.</p>

**PLANS AND DOCUMENTS referred to in the SDA APPROVAL**



**SDA approval: AP2023/005**



Performance Outcomes	Acceptable Outcomes	Compliance
	<p>Development does not result in the ingress of saline water into freshwater aquifers.</p> <p><b>Note:</b> Where development is likely to impact on the water table, a hydrological assessment undertaken by a suitably qualified professional may be required to demonstrate no adverse impact on the groundwater hydrological regime.</p>	
Excavation and filling		
<p>PO13</p> <p>The siting and design of earthworks minimises impacts on the natural landform that may cause contamination or interfere with the flow of a waterway or water supply source.</p>	<p>AO13.1</p> <p>Earthworks comply with the following locational criteria:</p> <ul style="list-style-type: none"> <li>a. 25m setback to a stream order 1–3;</li> <li>b. 50m setback to a stream order 4 or greater;</li> <li>c. 200m setback to a full supply level of a dam, lake or reservoir or watercourse which serves as a potable water supply;</li> <li>d. is not undertaken on land at or below the 1% AEP; and</li> <li>e. is not undertaken on a slope greater than 15%.</li> </ul>	<p><b>Complies.</b> Earthworks comply with the locational criteria and further an erosion and sediment control plan has been prepared in accordance with best practice which if followed will minimise movement of sediment off site.</p>
<p>PO14</p> <p>Any earthworks minimise erosion and the movement of sediment off-site.</p>	<p>No acceptable outcome is nominated.</p>	<p><b>Complies.</b> An erosion and sediment control plan has been prepared in accordance with best practice which if followed will minimise movement of sediment off site.</p>

Performance Outcomes	Acceptable Outcomes	Compliance
<p><b>Note:</b> A Sediment and Erosion Control Plan is to be prepared by a suitably qualified and experienced professional in accordance with best practice such as IECA 2008, Best Practice Erosion and Sediment Control.</p>		
<p>Dangerous goods, hazardous substances or environmentally hazardous materials</p>		
<p>PO15</p> <p>Dangerous goods, hazardous substances or environmentally hazardous materials are stored and handled in a manner that minimises the potential for contamination of surface and groundwater in the event of a leak or spill.</p>	<p>AO15.1</p> <p>The storage or handling of dangerous goods, hazardous substances or environmentally hazardous materials involves an aggregate quantity less than 200L or 200kg.</p> <p>OR</p> <p>AO15.2</p> <p>The storage or handling of dangerous goods, hazardous substances or environmentally hazardous materials with an aggregate quantity greater than 200L or 200kg and less than 1000L or 1000kg maintains the following separation distances:</p> <ul style="list-style-type: none"> <li>a. 100m to a minor waterway;</li> <li>b. 100m to a stream order 4 or greater; and</li> <li>c. 800m to a full supply level of a dam, lake or reservoir or watercourse that serves as a potable water supply.</li> </ul> <p>AND</p>	<p><b>Complies.</b> Dangerous goods, hazardous substances or environmentally hazardous materials greater than a 200L or 200kg and less than 1000L or 1000kg may be stored or handled on site from time to time. All dangerous goods, hazardous substances or environmentally hazardous materials will be appropriately stored, undercover, within the heavy machinery shed located more than 100m from Sandy Creek, above the 1% AEP and bunded via secondary containment to recover spills and in accordance with <i>Australian Standard AS 1940-2004: The Storage and Handling of Flammable and Combustible Liquids</i>.</p> <p>The storage of petroleum products in bulk (diesel – 30,000L and adblue 5000L) will be aboveground in self-bunded vessels that meet <i>Australian Standard AS 1692 Steel Tanks for Flammable and Combustible Liquids</i>. Refer to drawings ACS-230008-GEN-07.</p>

PLANS AND DOCUMENTS referred to in the SDA APPROVAL




SDA approval: AP2023/005



Performance Outcomes	Acceptable Outcomes	Compliance
	<p>AO15.3</p> <p>Dangerous goods, hazardous substances or environmentally hazardous materials are located and stored in the following manner:</p> <ul style="list-style-type: none"> <li>a. is not undertaken on land within the 1% AEP flood event;</li> <li>b. undercover in a building or similar structure;</li> <li>c. in or on a dedicated impervious secondary containment store or device that permits full recovery of spills;</li> <li>d. in a manner that prevents the movement of packages/containers from their place of storage during a flood event; and</li> <li>e. in accordance with Australian Standard AS 1940-2004: The Storage and Handling of Flammable and Combustible Liquids.</li> </ul> <p>OR</p> <p>AO15.4</p> <p>The storage of dangerous goods, hazardous substances or environmentally hazardous materials (other than petroleum products) in aggregate quantities greater than 1000L or 1000kg is not undertaken unless a site-specific risk assessment presents minimal risk to drinking water quality.</p>	

**PLANS AND DOCUMENTS**  
 referred to in the  
**SDA APPROVAL**




SDA approval: AP2023/005

Performance Outcomes	Acceptable Outcomes	Compliance
	<p>For petroleum products only:</p> <p>AO15.5</p> <p>The storage of petroleum products in bulk (greater than 1000L) aboveground uses self-bunded vessels that meet <i>Australian Standard AS 1692 Steel Tanks for Flammable and Combustible Liquids</i>.</p> <p>OR</p> <p>AO15.6</p> <p>The storage of petroleum products in bulk (greater than 1000L) aboveground uses single-skin vessels installed within a bunded compound that:</p> <ul style="list-style-type: none"> <li>a. is sufficiently impervious (permeability should be &lt;10<sup>-9</sup> m/s) to retain and recover spillage; and</li> <li>b. has a net capacity of at least 100% of the bunded vessel or aggregate quantity of vessels where operated as a single unit.</li> </ul> <p>OR</p> <p>AO15.7</p> <p>Petroleum products below ground (greater than 200L) are stored in vessels that are non-corrodible, double walled with an interstitial space between, and meet the requirements of Australian Standard AS 1692: <i>Steel Tanks for Flammable and Combustible Liquids</i> and/or UL 1316 <i>Glass fibre reinforced plastic underground storage tanks for</i></p>	

**PLANS AND DOCUMENTS referred to in the SDA APPROVAL**


SDA approval: AP2023/005





Performance Outcomes	Acceptable Outcomes	Compliance
	<i>petroleum products, alcohols and alcohol gasoline mixture.</i>	
Material change of use for extractive industry only		
PO16  Extraction activities do not impact on erosion, natural fluvial processes, river bank stability or the storage capacity volume of a floodplain.	No acceptable outcome is nominated.	Not applicable.
For reconfiguring a lot only		
PO17  When reconfiguring a lot, all resultant lots requiring an on-site wastewater treatment system do not compromise the environmental values of drinking water supply.  <b>Note:</b> Drinking water supply environmental values are referenced within Schedule 1 of the <i>Environmental Protection Policy (Water) 2009</i> .	AO17.1  Any new lot can accommodate an area for on-site wastewater treatment and disposal complying with the following:  a. 50m setback to a stream order 1–3;  b. 100m setback to a stream order 4 or greater; and  c. 400m setback to a full supply level of a dam, lake or reservoir or watercourse that serves as a potable water supply.  AND  AO17.2  Any new lot can accommodate an area for on-site wastewater treatment and disposal on land that is not within the 1% AEP flood event and on a slope at or less than 10%.	Not applicable.


**PLANS AND DOCUMENTS referred to in the SDA APPROVAL**



**SDA approval: AP2023/005**

Performance Outcomes	Acceptable Outcomes	Compliance
	<p>AND</p> <p>AO17.3</p> <p>Any proposed lots that are to accommodate a future on-site wastewater system, maintain an average lot size of at least 2.5 ha.</p> <p><b>Note:</b> A wastewater site analysis is to be prepared by a suitably qualified professional demonstrating the above.</p>	

PLANS AND DOCUMENTS  
 referred to in the  
 SDA APPROVAL



SDA approval: AP2023/005




**Appendix C) Effluent Disposal Report**

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval: AP2023/005**



STAV'S HYDRAULIC SERVICES  
ABN: 64 467 212 730  
QBCC: 15061807  
[stephen@stavs.com.au](mailto:stephen@stavs.com.au)  
[www.stavs.com.au](http://www.stavs.com.au)  
0402 303 599

## **SITE & SOIL EVALUATION REPORT 590 SANDY CREEK ROAD, JOSEPHVILLE**

<b>Prepared for:</b>	Matthew Haack C/o ACS Engineers
<b>Prepared by:</b>	Stav's Hydraulic Services
<b>Purpose:</b>	Site & Soil Evaluation Report
<b>Issue No:</b>	C
<b>Date Issued:</b>	16-Jan-24
<b>Author:</b>	Stephen Stavrinou

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**




**SDA approval:** AP2023/005



1. Contents

- 2. Intro..... 3
- 3. Executive summary..... 3
- 4. Site Investigation ..... 4
- 5. Effluent Quality and Control Parameters ..... 5
- 6. Design Calculations ..... 5
- 7. Operation and Maintenance ..... 7
- 8. Appendix A - Land application area Vegetation ..... 8
- 9. Appendix B - Land application area plan..... 9

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005

## 2. Intro

Stav's Hydraulic Services have carried out a Site and Soil Evaluation for the On-Site waste water treatment and the effluent disposal at Lot 1 on RP32191 - 590 Sandy Creek Road, Josephville, Qld.

The following report has been prepared in accordance with AS/NZS1547:2012, On-Site Domestic Waste Water Management and the Queensland Plumbing and Waste Water Code.

## 3. Executive summary

The recommendation and comments:

1. Use an Advanced Secondary all-waste sewage system such as the CivilMart 1T-AST concrete precast 10EP advanced Secondary Wastewater treatment system c/w nutrient reduction.
2. The peak daily design volume for the entire site is 8 Equivalent persons – 1,200l/day – loads from main residence, caretakers & shed.
3. Soil is a densely structured category 5 – Clayey Sand, Low Plasticity, Fine Grained, yellow - Design Irrigation Rate (DIR) = 21 mm / week
4. Total land application to be comprised of a land application area of 400m<sup>2</sup> via drippers.
5. Have warning signs, complying with AS1319 at the boundaries of the designated area in two places and clearly visible to property users with wording such as “Recycled Water – Avoid Contact – DO NOT DRINK”
6. On-site sewage systems are not designed to cope with the flow from garbage grinders, fats, oils or chemicals and household cleaning products are to be used in accordance with their labels.
7. The land application area is an important area and has to be maintained e.g. regularly mowed, do not drive vehicles over the area or allow livestock to access the land application area Follow the maintenance requirements specified by the manufacturer and authorised service agent.

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval: AP2023/005**



## 4. Site Investigation

Site Investigation	
Date of Investigation	16.06.2023
Address	590 Sandy Creek Road, Josephville
Area of Site	380,780m <sup>2</sup>
Property Description	Lot 1 on RP32191
Local Council	Scenic Rim Regional Council
Weather	Fine
Ground Cover	Grass
Well/Bores	0
Waterways	Existing Dams on site
Water Table	Nil
Embankments	Nil
Buildings	Farm sheds to rear bottom of site
Site Exposure	Full Sunlight
Boundaries	Sufficient
Landscape Description	Waxing Divergent
Diversion / Retention Mound	Nil
Ground Water Cut off drains	Nil
Intended Water Supply	Rain Water

Soil Characteristics	
Borehole	
Depth	0-600mm
Texture - structure - Colour	Silty Sand Loam in the top layers that increase in clay content with depth
Soil Category	5
Indicative permeability (Ksat) m/day	0.71
Design Loading Rate (DLR) mm/week	21
Test pit	1m depth
Test pit	
Depth	1m
Water	Nil
Bedrock	Nil

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005

## 5. Effluent Quality and Control Parameters

Effluent Quality Parameters			
Parameter	Primary	Secondary	Advanced Secondary
Bods	120-240	20	10
Total Suspended Solids (mg/L)	65-180	30	10
Thermotolerant Coliforms (org/100mL)	N/A	200	10

## 6. Design Calculations

Design Loadings - Main Residence			
No. of Bedrooms	4		
Equivalent Persons (EP)	6		
Design Flow L/day	120	Tank Water Supply	
Daily flow / Weekly Flow	720	/	5040
Design Loading Rate (DLR) mm/week	21		
Land Application Area (m <sup>2</sup> )	240 m <sup>2</sup>	Adopt	240 m <sup>2</sup>
Design Loadings - Caretakers Residence			
No. of Bedrooms	2		
Equivalent Persons (EP)	3		
Design Flow L/day	120	Tank Water Supply	
Daily flow / Weekly Flow	360	/	2520
Design Loading Rate (DLR) mm/week	21		
Land Application Area (m <sup>2</sup> )	120 m <sup>2</sup>	Adopt	120 m <sup>2</sup>
Design Loadings - Shed			
No. of Staff	4		
Design Flow L/day	30	Tank Water Supply	
Daily flow / Weekly Flow	120	/	840
Design Loading Rate (DLR) mm/week	21		
Land Application Area (m <sup>2</sup> )	40 m <sup>2</sup>	Adopt	40 m <sup>2</sup>

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005



<b>Bod5 Applied</b>	
Bod5 Applied 10mg / litre/ day	4.38 kg/year
Soil Absorption Only	0.05kg / m <sup>2</sup> / year
Minimum land Application Area	87.6 m <sup>2</sup>

The proposed wastewater system utilises an Advanced Secondary all-waste sewage treatment plant - CivilMart 1T-AST concrete precast 10EP advanced Secondary Wastewater treatment system c/w nutrient reduction (chlorine dosing).

The Proposed system will discharge to drippers as per below calculations.

<b>Compensating Dripper Calculations</b>		
Compensation Dripper	400	36 m lateral length
No. of Laterals and Spacing's	11	1 m centres
Dripper Hole spacing	0.5	m dripper hole spacing
Compensating dripper flow rate		2.5 l/hour dripper rate
Effluent Flow Rate		792 l/hour
Effluent Transfer	8 transfers @	11 min/transfer

**AS1547 states that:**

- a. The effluent is required to be evenly distributed within the designated area.
- b. Have warning, complying with AS1319 at the boundaries of the designated area in two places and clearly visible to property users with wording such as "Recycled Water – Avoid Contact – DO NOT DRINK"
- c. Ensure that the effluent does not come into contact with people, domestic animals, fruit or vegetables for human consumption

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval: AP2023/005**

## **7. Operation and Maintenance**

Maintenance requirements specified by the manufacturer and authorized service agent are to be implemented. These include:

- Use low sodium biodegradable soaps and detergents
- No paints, solvents, chemicals, food scraps, fats, oils or any other solids are not to be disposed of "down the drain"
- On-site sewage systems are not designed to cope with the flow from garbage grinders
- The land application area is an important area and has to be maintained e.g. regularly mowed or pruned also ensuring that there is no ponding of effluent in the disposal area
- Vehicles, livestock or general access is to be generally restricted with warning signs erected

**PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL**



**SDA approval: AP2023/005**



## 8. Appendix A - Land application area Vegetation

Vegetation for Land Application Area		
Recommended Species: Callistemon, Melaleuca, Lomandra and Casuarina		
Vegetation Form	Botanical Name	Common Name
Ground cover / grasses / clumping	Belechnum SPP	Water ferns
	Lomandra Longiflora	Matt rush
	Themeda Triandra	Kangaroo grass
	Viola Hederacea	Native violet
	Dianella Caurulea	Paroo lily
	Gahnia SPP	Sword grass
Vines	<u>Cissus Antarctica</u>	Kangaroo vine
	Cissus Hypoglauca	Water vine
	Hibbertia Scandens	Guinea flower
Shrubs	<u>Callistemon Pachyphylus</u>	Swamp callistemon
	Callistemon Salignus	Pink tips
	Leptospermum Speciosum	Coastal tea tree
	Leptospermum Flavescens	Weeping tea tree
	Melastoma Affine	Native lasiandra
Small Trees	<u>Melicope Elleryana</u>	Corkwood
	Melaleuca Thymifolia	Pink or white lace
	Melaleuca Sheberi	Paperbark
	Melaleuca Nodosa	Paperbark
	Melaleuca Dealbata	White bolly gum
	Archontophoenix Cunninghamiana	Picabeen or Bangalow plam
	Eucalyptus Congiomerata	Swamp stringy bark
	Eucalyptus Intermedia	Pink bloodwood
	Glochidion Sumatranum	Umbrella cheese tree
	Hymenosporum Flavum	Native frangipani
	Livistonia Australis	Cabbage palm
	Lophostermon Suaveolens	Swamp turpentine
	Melaleuca Quinquenervia	Broadleaf paperbark
	Syzygium SPP	Lillypillies


PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005

9. Appendix B - Land application area plan

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005



# EFFLUENT DISPOSAL


590 SANDY CREEK ROAD,  
JOSEPHVILLE QLD 4285



## DRAWING LIST

- H101 - COVER SHEET & LOCATION PLAN
- H102 - LEGEND, NOTES & DETAILS
- H103 - SITE PLAN EFFLUENT DISPOSAL LAYOUT
- H104 - WASHBAY LAYOUT

PROJECT LOCATION



LOCATION PLAN

NOT TO SCALE

2m 0 2m 4m 6m 8m 10m

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005

ISSUE	AMENDMENT	DATE	CLIENT:
P1	PRELIMINARY ISSUE	16.06.2023	MATTHEW HAACK C/o ACS ENGINEERS
A	APPROVAL ISSUE	19.06.2023	

DESIGNER: STEPHEN STAVRINOU QBCC 15061807

CONSULTANT:



07 5623 4177

www.stavs.com.au

shs@stavs.com.au

PO Box 529,

Jimboomba, Qld


PROJECT:

**SITE & SOIL EVALUATION  
REPORT**  
LOT 1 ON RP32191  
590 SANDY CREEK ROAD,  
JOSEPHVILLE

TITLE:

HYDRAULIC SERVICES  
COVER SHEET & LOCATION PLAN

PROJECT No.	ACS28	DRAWING No.	ISSUE No.
SCALE / SIZE:	N.T.S @ A3	H101	A



**FLUSHING VALVE DETAIL**

SCALE: NTS

**GENERAL**

1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF AS3500, THE BUILDING CODE OF AUSTRALIA, RELEVANT AUSTRALIAN STANDARDS AND THE LOCAL AUTHORITY REQUIREMENTS.
2. THESE PLANS SHALL BE READ IN CONJUNCTION WITH THE APPROVED ARCHITECTURAL AND RELEVANT SERVICES PLANS AND SPECIFICATIONS
3. LOCATION OF EXISTING SERVICES HAS BEEN DETERMINED FROM SITE VISITS AND EXISTING RECORD PLANS. NO PROVING OF SERVICES HAS BEEN UNDERTAKEN. THE CONTRACTOR SHALL PROVE ALL SERVICES PRIOR TO COMMENCING CONSTRUCTION AND ADVISE THE SUPERINTENDENT OF ANY DISCREPANCIES BEFORE PROCEEDING. THIS CONTRACTOR MUST CO-ORDINATE WITH ALL OTHER SERVICES. PIPEWORK SHOWN ON THIS DRAWING IS DIAGRAMMATIC ONLY. FINAL LOCATION OF SERVICES SHALL BE DETERMINED ON SITE.
4. ARRANGE & APPLY TO THE LOCAL AUTHORITY FOR ALL NECESSARY PERMITS. PAY ALL PLUMBING INSPECTION FEES AND CHARGES, OBTAIN COMPLETION CERTIFICATE AND SUBMIT TO SUPERVISOR.
5. THE ENTIRE HYDRAULIC SERVICES INSTALLATION AND EQUIPMENT SHALL BE MAINTAINED UNDER WARRANTY FOR A PERIOD OF TWELVE (12) MONTHS AFTER PRACTICAL COMPLETION HAS BEEN ACHIEVED.
6. PROVIDE INSTRUCTIONS MANUALS AT PRACTICAL COMPLETION. CONTAINING THE FOLLOWING:
  - GENERAL DESCRIPTION OF PROJECT
  - LISTING OF EQUIPMENT, MANUFACTURERS NAMES, AGENTS ETC.
  - OPERATING AND MAINTENANCE INSTRUCTIONS AND WARRANTY INFORMATION FOR EACH ITEM OF EQUIPMENT.
  - "AS CONSTRUCTED" DRAWINGS.
  - COUNCIL INSPECTION REPORTS AND FINAL COMPLETION CERTIFICATES FROM RELEVANT AUTHORITIES.

**WATER**

1. ALL EXPOSED HW & CW PIPEWORK SHALL BE COPPER TUBE TYPE "B" TO AS1432. CONNECT COPPER PIPE WITH BRAZED JOINTS IN AS1645 OR COMPRESSION JOINTS AS1585. USE PRE-INSULATED PIPEWORK FOR HOT WATER SERVICES OR INSULATE WITH 'ARMAFLEX' INSULATION OR SIMILAR. DENSOWRAP ALL CW PIPEWORK IN-GROUND. PROVIDE INSULATION TO ALL HOT WATER PIPEWORK. PROVIDE ALL NECESSARY ALLOWANCES FOR THERMAL MOVEMENT OF PIPES.
2. WATER SUPPLY PIPEWORK CONCEALED IN WALLS AND EXTERNAL TO BUILDING IN-GROUND MAY BE POLYETHYLENE PIPE OF MIN. CLASS 12, AND SHALL COMPLY WITH AS 1159. INSTALLATION OF POLYETHYLENE PIPES SHALL BE IN ACCORDANCE WITH AS 2033 AND THE MANUFACTURERS SPECIFICATIONS.
3. TAKE ALL NECESSARY PRECAUTIONS TO PREVENT WATER HAMMER AND RECTIFY SHOULD IT OCCUR.
4. EXTERNAL AND INTERNAL HOSE COCKS SHALL BE FITTED WITH HOSE TYPE VACUUM BREAKERS.
5. PROVIDE HW & CW STOPCOCKS TO ALL HW & CW FIXTURES.
6. ALL PIPEWORK TO BE IDENTIFIED IN ACCORDANCE WITH AS1345.
7. ALL PIPE DIAMETERS NOMINATED ARE NOMINAL BORE DIAMETERS UNLESS NOTED OTHERWISE.

**ON SITE DISPOSAL NOTES**


1. IRRIGATION SYSTEM TO COMPLY WITH AS1547, QLD PLUMBING WASTE WATER CODE, ASSOCIATED DOCUMENTATION AND MANUFACTURERS SPECIFICATIONS.
2. MINIMUM COVER OVER RISING MAIN 450mm. RISING MAINS TO BE 32Ø PIPES TO AS/NZS 1477. PIPE TO BE LILAC COLORED AND/OR INSTALLED WITH TAPE IDENTIFYING THE PIPES CONTENTS AS SEWAGE EFFLUENT.
3. IRRIGATION SYSTEMS DISTRIBUTE EFFLUENT INTO THE TOPSOIL LAYERS TO PROVIDE IN-SOIL TREATMENT OF THE REMAINING EFFLUENT RESIDUALS AS WELL AS PROVIDE NUTRIENT UPTAKE AND EVAPOTRANSPIRATION BY GRASS, SHRUBS OR PLANTINGS. THE CHOSEN GRASS, SHRUBS OR PLANTINGS SHALL BE PLANTED/SEEDED PRIOR TO THE COMMISSIONING OF THE SYSTEM TO ALLOW FOR PROPER EFFLUENT DISPOSAL.

**DRAINAGE**

1. SANITARY DRAINAGE & VENT PIPEWORK IN UPVC IN ACCORDANCE WITH AS1260 AND THE MANUFACTURERS SPECIFICATIONS.
2. ALL PIPEWORK TO BE IDENTIFIED IN ACCORDANCE WITH AS1345.
3. ALL PIPE DIAMETERS NOMINATED ARE NOMINAL BORE DIAMETERS UNLESS NOTED OTHERWISE.


**LEGEND**

— R — R —	PUMPED EFFLUENT
—————	SANITARY DRAINAGE PIPEWORK
- - - - -	VENT PIPEWORK
- · - · - ·	STORMWATER PIPEWORK
- · - · - · - · - · - ·	COLD WATER PIPEWORK
- · - · - · - · - · - · - · - · - ·	HOT WATER PIPEWORK
⊗	VALVE
AFFL	ABOVE FINISHED FLOOR LEVEL
AHD	AUSTRALIAN HEIGHT DATUM
B	BASIN
CD	CONDENSATE DRAIN
COS	CLEAR OUT TO SURFACE
Cu	COPPER PIPE
CW	COLD WATER
CV	CONTROL VALVE
DP	DOWN PIPE
DW	DISHWASHER
e	EXISTING TO REMAIN
FFL	FINISHED FLOOR LEVEL
FW	FLOOR WASTE GULLY (c/w REMOVABLE CHROME GRATE)
H/L	HIGH LEVEL
HC	HOSE COCK c/w KEY OPERATED HANDLE
HW	HOT WATER
HWH	HOT WATER HEATER
IC	INSPECTION CHAMBER
IO	INSPECTION OPENING
L/L	LOW LEVEL
ORG	OVERFLOW RELIEF GULLY
SHR	SHOWER
SK	SINK
WC	WATER CLOSET
VB	VACUUM BREAKER




ISSUE	AMENDMENT	DATE	CLIENT:	CONSULTANT:	PROJECT:	TITLE:	
P1	PRELIMINARY ISSUE	16.06.2023	MATTHEW HAACK C/O ACS ENGINEERS	 07 5623 4177 www.stavs.com.au shs@stavs.com.au PO Box 529, Jimboomba, Qld	SITE & SOIL EVALUATION REPORT LOT 1 ON RP32191 590 SANDY CREEK ROAD, JOSEPHVILLE	HYDRAULIC SERVICES LEGEND, NOTES & DETAILS	
A	APPROVAL ISSUE	19.06.2023					
DESIGNER: STEPHEN STAVRINOU QBCC 15061807						PROJECT No. ACS28 SCALE / SIZE: NTS @ A3	DRAWING No. H102 ISSUE No. A





PLANS AND DOCUMENTS referred to in the SDA APPROVAL

SDA approval: AP2023/005



2m 0 2m 4m 6m 8m 10m

ISSUE	AMENDMENT	DATE
P1	PRELIMINARY ISSUE	16.06.2023
A	APPROVAL ISSUE	19.06.2023
B	LAA AMENDED	18.12.2023
C	LAA AMENDED	17.01.2024

CLIENT: **MATTHEW HAACK C/O ACS ENGINEERS**

CONSULTANT:




STAV'S HYDRAULIC SERVICES

07 5623 4177  
www.stavs.com.au  
shs@stavs.com.au  
PO Box 529,  
Jimboomba, Qld

PROJECT: **SITE & SOIL EVALUATION REPORT**  
**LOT 1 ON RP32191**  
**590 SANDY CREEK ROAD,**  
**JOSEPHVILLE**

TITLE:	
HYDRAULIC SERVICES SITE PLAN EFFLUENT DISPOSAL LAYOUT	
PROJECT No.	ACS28
SCALE / SIZE:	1:1000 @ A3
DRAWING No.	H103
ISSUE No.	C

DESIGNER: STEPHEN STAVRINOU QBCC 15061807



CAM LOCK SUCTION LINES CONNECTED TO BASE OF HOLDING TANKS. TERMINATE 1200 AFFL. PROVIDE MECHANICAL PROTECTION.

Ø100 HOLDING TANK VENT & DRAIN VENT TO RISE UP ON WALL. PROVIDE MECHANICAL PROTECTION.

1000L OIL HOLDING TANK CONNECTED TO SERVICE PIT SUMP.

FOX ENVIRONMENTAL SYSTEMS FF600 STORMWATER DIVERSION DEVICE.

FIRST FLUSH & STORMWATER DIVERSION CONNECTION TO CIVIL SYSTEM.

10,000L HOLDING TANK c/w ANTI FLOTATION BASE. PROVIDE HIGH LEVEL ALARM SET AT 8,000L AND HIGH LEVEL ALARM SET AT 10,000L TO ISOLATE THE FOX SOLENOID ON THE INCOMING WASHBAY WATER SUPPLY.

FOX ENVIRONMENTAL SYSTEMS FF600 STORMWATER DIVERSION DEVICE.

FIRST FLUSH & STORMWATER DIVERSION CONNECTION TO CIVIL SYSTEM.

ISSUE	AMENDMENT	DATE
A	APPROVAL ISSUE	18.12.2023
B	OIL SEPARATOR ADDED	17.01.2024

CLIENT:  
**MATTHEW HAACK C/o  
ACS ENGINEERS**

CONSULTANT:  
**SHS**  
STAV'S HYDRAULIC SERVICES  
07 5623 4177  
www.stavs.com.au  
shs@stavs.com.au  
PO Box 529,  
Jimboomba, Qld

PROJECT:  
**SITE & SOIL EVALUATION  
REPORT  
LOT 1 ON RP32191  
590 SANDY CREEK ROAD,  
JOSEPHVILLE**

TITLE:		DRAWING No.   ISSUE No.	
HYDRAULIC SERVICES PART SITE PLAN WASH BAY LAYOUT		H104	B
PROJECT No.	ACS28	SCALE / SIZE: 1:500 @ A3	



**Appendix D) LURT Output**

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval: AP2023/005**

# Rating Details

## Property Owner Details

Property Owner:	"MJ Haack Family Trust C/- ACS Engineers"			
Postal Address:	"7 Church Stret"	"Boonah"	"QLD"	"4310"
Phone Number:	"0755413500"	Mobile Number:	"0466800355"	
Email:	"matthew@acsengineer.com.au"			

## Property Details

Street Address:	"590 Sandy Creek Road"	"Josephville"	"QLD"	"4285"
Latitude:	""	Longitude:	""	
Lot Number:	""	Plan Number:	""	
Area (m2):	"380780"	Local Government:	"Scenic Rim Regional Council"	

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005



# Rating Risk Rating Questionnaire

Unmitigated Score	No further mitigation required	Mitigated Score
14		6
<b>MEDIUM</b>		
<b>Calculating Unmitigated Risk</b>		
1	<p>Does the disposal area and wastewater treatment system maintain the following separation distances (AND):</p> <ul style="list-style-type: none"> <li>At least 100m to the nearest watercourse (permanent and non-permanent)?</li> <li>At least 400m from the full supply level of a potable water supply?</li> </ul> <p>Please note: Potable water supply includes any dam, bore, reservoir or conduit used for direct extraction of water for drinking water purposes.</p>	No
2	<p>Is the disposal area or the wastewater treatment system (OR):</p> <ul style="list-style-type: none"> <li>Less than 50m to the nearest watercourse (permanent and non-permanent)?</li> <li>Less than 200m from the nearest full supply level of a potable water supply?</li> </ul> <p>Please note: Potable water supply includes any dam, bore, reservoir or conduit used for direct extraction of water for drinking water purposes.</p>	No
3	Is the disposal area of wastewater treatment system located inside of a defined flood event (Council or State mapping), at a minimum being 1% Annual Exceedance Probability (AEP)?	No
4	What is the maximum slope of the disposal area or wastewater treatment system location?	<5%
5	How many bedrooms are serviced by the proposed wastewater treatment system?	3 or more bedrooms
6	Is the indicative permeability range higher than 1m/day?	No
7	Is the separation distance to the water table/bedrock as specific for the type of system and at a minimum 1m below the disposal depth?	Yes
8	Is the dwelling a permanent or holiday residence?	Permanent Residence
9	Is the indicative drainage class either poorly drained (Soil Category 5) or very poorly drained (Soil Category 6), as defined in Australian Standard AS1547?	Yes
10	Does the proposal involve composting?	No composting
11	Please select an irrigation method.	Absorption
12	Please select the proposed treatment method.	Aerated
13	Does the system propose the diversion or re-use of greywater?	No
<b>Mitigation Reduction:</b>		<b>8</b>

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval:** AP2023/005

# Model Conditions

## Here are your draft conditions!

1	The poor drainage of the soil necessitates an appropriate depth of topsoil over the proposed effluent disposal area. Either soil remediation (gypsum / scarification) or clean imported topsoil must be provided to a depth of 150mm – 250mm over the disposal area and scarified into soils over the entire disposal area to ensure adequate drainage and reduction of nutrients.
2	The disposal area must be planted with kikuyu grass or other native vegetation which provides a high uptake of nitrogen and phosphorus and prevents erosion.
3	The disposal area must incorporate appropriate diversion drainage above the disposal area (to prevent stormwater inundation) and bunds below the disposal area to reduce the risk of waterway contamination.
4	To minimise the risk of failure or inefficiency, the wastewater treatment system and disposal area must be inspected and serviced by an appropriately qualified professional in accordance with the manufacturer's recommendations and at least annually.
5	Ensure that larger deep-rooting plants and trees which may block sunlight are not planted near the disposal area to reduce the chance of root intrusion and clogging and maximise sun exposure.
6	A 100% reserve area is reserved and maintained on-site to allow for an alternative disposal location in case of land application area failure, malfunction or loss of soil uptake capacity. The reserve area must be kept clear of buildings, structures, vehicular movement paths or other activities which may otherwise affect its use for effluent disposal in the future.
7	No vehicular, machinery or domestic animal traffic movement is to occur over the disposal area, to maintain the integrity and function of sub-surface pipelines. Barriers such as fencing or shrubs are to be used when necessary.
8	The design must incorporate a warning system to notify of pump failure and/or high water level comprising of a highly visible strobe warning light at the tank and an internal alarm mounted in the house comprising of an audible and visual. A licenced plumber/service provider must be contacted as soon as practical after an alarm activates to rectify the issue.
9	The treatment system must incorporate contingency components including a backup pump stored appropriately on the site.
10	The wastewater treatment system must be an advanced secondary wastewater treatment system with nutrient removal with Chief Executive approval from the Department of Energy and Public Works and incorporate chlorination. The wastewater treatment system and disposal area must be designed operated and maintained in accordance with manufacturers specifications and the submitted Wastewater Design Report.

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005

## Appendix E) Rational Method Calculations

### Catchment Details

Name	Pre-Developed	Post-Developed
Catchment Area (ha)	38	38
Stream Length (m)	200	200
Sheet flow length (m)	200	200
Slope (%)	10	10
Hortons N Value	0.05	0.05
Tc Sheet flow	19.7	19.7
Tc channel flow	2.2	2.2
Total time of conc. (tc)	<b>22.0</b>	<b>22.0</b>

### Rainfall Intensities

63%	56.3	56.3
50%#	63.7	63.7
20%*	86.8	86.8
10%	102.4	102.4
5%	117.6	117.6
2%	137.5	137.5
1%	152.7	152.7

### Rainfall Depth

63%	20.6	20.6
50%#	23.3	23.3
20%*	31.8	31.8
10%	37.6	37.6
5%	43.1	43.1
2%	50.4	50.4
1%	56.0	56.0
Fraction impervious	0.00000	0.01910
C10 runoff coefficient	0.63	0.63

### Frequency Factors

FF, 1-year	0.8	0.8
FF, 2-year	0.85	0.85
FF, 5-year	0.95	0.95
FF, 10-year	1	1
FF, 20-year	1.05	1.05
FF, 50-year	1.15	1.15
FF, 100-year	1.2	1.2

### Flow Calculations

**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



SDA approval: AP2023/005



63.2% (m <sup>3</sup> /s)	2.996	2.996
50% (m <sup>3</sup> /s)	3.602	3.602
20% (m <sup>3</sup> /s)	5.487	5.487
10% (m <sup>3</sup> /s)	6.817	6.817
5% (m <sup>3</sup> /s)	8.220	8.220
2% (m <sup>3</sup> /s)	10.526	10.526
1% (m <sup>3</sup> /s)	12.198	12.198

### Runoff Volume Estimation

Name	Pre-Developed	Post-Developed
Catchment Area (ha)	38	38
Cv(pervious)	0.63	0.63
Area Impervious	0	0.72596
Cv Composite	0.630	0.637

### Runoff Volume Estimation - single storm

63.2% Volume (m <sup>3</sup> )	4940.1	4995.5
50% Volume (m <sup>3</sup> )	5588.9	5651.6
20% Volume (m <sup>3</sup> )	7618.6	7704.1
10% Volume (m <sup>3</sup> )	8990.8	9091.7
5% Volume (m <sup>3</sup> )	10325.0	10440.9
2% Volume (m <sup>3</sup> )	12072.6	12208.1
1% Volume (m <sup>3</sup> )	13407.5	13557.9

### Change in Volume

63.2% Volume (m <sup>3</sup> )		55.4
50% Volume (m <sup>3</sup> )		62.7
20% Volume (m <sup>3</sup> )		85.5
10% Volume (m <sup>3</sup> )		100.9
5% Volume (m <sup>3</sup> )		115.8
2% Volume (m <sup>3</sup> )		135.5
1% Volume (m <sup>3</sup> )		150.4

PLANS AND DOCUMENTS  
referred to in the  
SDA APPROVAL



SDA approval: AP2023/005

# FONTAINE 60

🚗 4 | 🏠 3 | 🚗 5 | 🚗 2

fits  
**41.5m**  
block width\*



## Home area

Total area	557.67m <sup>2</sup>
House area	375.36m <sup>2</sup>
Garage	56.04m <sup>2</sup>
Outdoor room	89.66m <sup>2</sup>
Portico	20.95m <sup>2</sup>

## Ground floor

Double garage	6.13 x 6.51m
Outdoor Room 1	59 x 6.47m
Porch	5.27 x 1.32m
Sitting	4.33 x 5.41m
Family	7.39 x 7.52m
Leisure	3.2 x 4.87m
Retreat	3.49 x 3.38m
Home theatre	4.68 x 4.54m
Master suite	4.81 x 5.55m
Bedroom 2	3.91 x 4.54m
Bedroom 3	3.66 x 3.58m
Bedroom 4	4.18 x 3.75m
Workshop	2.99 x 3.82m

## Other design options

At Metricon, we understand that crafting a home to perfectly suit your lifestyle is important. We have a variety of home designs and floorplan options for you to choose from.

Speak to your New Home Advisor today.


**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**




**SDA approval:** AP2023/005

\*Subject to orientation and fall of land and developer and council guidelines. Traditional floorplan shown.

# Stage 1 shed plans - concept



PLANS AND DOCUMENTS referred to in the SDA APPROVAL



SDA approval: AP2023/005








# Shed elevations - concept

PLANS AND DOCUMENTS referred to in the SDA APPROVAL




SDA approval: AP2023/005







PLAN




Left Elevation



Front Elevation




Right Elevation



Rear Elevation

PLANS AND DOCUMENTS referred to in the SDA APPROVAL

SDA approval: AP2023/005





CLIENT	
Portal Frame Gable Roof-Open Industrial Design Vdes=49 m/s (Reg-B) 18.000 x 18.000 x 6.000	
At: 585 Sandy creek road Josephville 4285	
For: Matt	
Approved by:	Date:

DRAWING		
QP1	Ref: 31121311590445	NTS
ARCHITECTURAL DRAWINGS		

# Bribie

## Area

House:	61.94 sqm
Porch:	5.15 sqm
Alfresco:	6.41 sqm
Total:	73.50 sqm



**PLANS AND DOCUMENTS**  
referred to in the  
**SDA APPROVAL**



**SDA approval:** AP2023/005

### EASTCOAST HOMES & PARK CABINS

32 Wheeler Crescent Currumbin Waters  
QLD 4223

P: 07 5598 1558

F: 07 5525 6475

E: info@eastcoasthomes.com.au



**Disclaimer**

Photographs & illustrations are intended to be a visual aid only. Eastcoast Homes & Park Cabins gives no warranty and makes no representation to the accuracy or sufficiency of any description, illustrations, photographs or statements contained in this brochure and accepts no liability for any loss suffered by any person who relies wholly or partly upon the information presented. All information is subject to change without notice © Copyright 2012

Plot Date: 8/11/2012 Drawn By: MB