


1:6000

D 01



NOTE:

THE FOLLOWING TBC WITH CLIENT PRIOR TO ANY INSTALL

- FAN CONFIGURATION
- MINI-VENT CONFIGURATION
- HEATER POSITIONS
- MINIMUM VENTILATION FAN CONFIGURATION TO BE CONFIRMED


PLANS AND DOCUMENTS referred to in the SDA APPROVAL



SDA approval: APC2022/005

NOTE:

- WALL BRACING ON BAYS 01, 21 AND 40
 - DRAIN IN SIDE WALLS BAY # 08, 12, 14, 16, 21, 24, 28, 32, 36 & 40 x AT EACH END WALLS
- ALL SIDE PA DOORS ARE IN CENTRE OF THE BAY U.N.O.



	DOOR SCHEDULE PER SHED									
	DOOR	op "	DECORPORA		\A.F. -	Head	Sill	Bollard		
Level	NUMBER	SP#	DESCRIPTION	Height	Width	Height	Height	Number		
RL	D01	SP 905	SP 905 - DOUBLE BARN DOOR WITH PA DOOR INSET: 3200H x 3600W (LEAF SIZE)	3200	3600	3200	0	SP 2173		
RL	D02	SP 339-B-2	SP 339-B - PA DOOR: 2040H x 750W (LEAF SIZE) - NO SILL	2040	750	2015	-25	-		
RL	D03	SP 339-B-2	SP 339-B - PA DOOR: 2040H x 750W (LEAF SIZE) - NO SILL	2040	750	2015	-25	-		
RL	D04	SP 340	SP 340 - PA DOOR: 1900H x 820W (LEAF SIZE)	1900	820	2050	150	SP 2479		
RL	D05	SP 340	SP 340 - PA DOOR: 1900H x 820W (LEAF SIZE)	1900	820	2050	150	SP 2479		
RL	D06	SP 340	SP 340 - PA DOOR: 1900H x 820W (LEAF SIZE)	1900	820	2050	150	SP 2170		
RL	D07	SP 340	SP 340 - PA DOOR: 1900H x 820W (LEAF SIZE)	1900	820	2050	150	SP 2479		
RL	D08	SP 339-B-2	SP 339-B - PA DOOR: 2040H x 750W (LEAF SIZE) - NO SILL	2040	750	2015	-25	SP 2170		
RL	D09	SP 339-B-2	SP 339-B - PA DOOR: 2040H x 750W (LEAF SIZE) - NO SILL	2040	750	2015	-25	-		
RL	D10	SP 341-B	SP 341- PA DOOR: 22100H x 920W (LEAF SIZE) - NO SILL	2210	920	2120	-90			
RL	D11	SP 341-B	SP 341- PA DOOR: 22100H x 920W (LEAF SIZE) - NO SILL	2210	920	2210	0	SP 2173		
RL	D12	SP 340	SP 340 - PA DOOR: 1900H x 820W (LEAF SIZE)	1900	820	2050	150			
TOTAL [OORS PER SHE	D: 12								

REFER TO "D 02 - "FARM LAYOUT" FOR INDIVIDUAL SHED ORIENTATION

AND CONFIRM WITH CLIENT BEFORE BUILD

WINDOW SCHEDULE PER SHED							
Level	WINDOW NUMBER	TYPE	DESCRIPTION	Height	Width	Head Height	Sill Height
RL	W01	0609	SLIDING GLASS WINDOW: 0609	600	900	1800	1200
Grand to	tal: 1						

PROPOSED NEW CONSTRUCTION - preliminary drawings



D 05

Phone:1300 815 888 (+61) 07 3281 3200 Fax: 1300 816 888 (+61) 07 3281 8295 Email: enquiries@santrev.com.au Web: www.santrev.com.au ABN: 43 124 970 878 BSA QLD: 1214566

SANTREV PTY LTD PO Box 95, Ipswich Queensland Australia 4305 ABN: 43 124 970 878
BSA QLD: 1214566
OCBA SA: 277785
BC VIC: CB-U 44246
© COPYRIGHT 2012 - SANTREV PTY LTD
THE IDEAS AND CONCEPTS CONTAINED WITHIN THIS
DOCUMENT AND THE DOCUMENT ITSELF REMAIN THE
INTELLECTUAL PROPERTY OF SANTREV PTY LTD AND
MAY NOT BE COPIED OR REPRODUCED IN PART OR IN
WHOLE WITHOUT EXPRESSED WHITTEN PERMISSION
FROM THE DIRECTORS OF SANTREV PTY LTD.

REV	DATE	
Α	CONCEPT DRAWINGS FOR REVIEW	12/10/2020
В	CONCEPT DRAWINGS FOR REVIEW	12/01/2020
С	CONCEPT DRAWINGS FOR REVIEW	13/01/2020
D	CONCEPT DRAWINGS FOR REVIEW	22/03/2020
Е	CONCEPT DRAWINGS FOR REVIEW	24/03/2020
F	CONCEPT DRAWINGS FOR REVIEW	19/04/2020

ALLAN CREEK POULTRY FARM

For:

Project Address:


LOT 50, 2215 BOONAH-BEAUDESERT ROAD, BROMELTON QLD


sheet title: BROILER SHED LAYOUT	
	sheet title:


Job no: Drawn by: AS


date: 19/04/2021


scale (A3): drawing no: **D 03**















SDA approval: APC2022/005

BOUR 9-5-17 PLANS AND DOCUMENTS referred to in the SDA APPROVAL



SDA approval: APC2022/005





Proposed Dwelling For Mr. M. TILLEY AT BOONAH ROAD. BEAUDESERT

FRANKLIN CONSTRUCTIONS

Beoudesert Business Pork Mt Lindesoy Highway Beoudesert 4285


BSA No. 727813 Phone 0755411301 Fax 0755411649



BURDING CONTRACTORS AND MANUFACTURERS OF STEEL FRANC HOMES

S	JOB No 662 DRAWING No 06-21	SCALE 1=100			
-	DATE 12-10-2006 DRAWN BY M. Boldwin	SHEET No 3			

Blue 9-5-17



Blue 4-577

GENERAL NOTES

- 1. THE CONTRACTOR IS TO VERIFY ALL SURFACE LEVELS. ANY DISCREPANCIES SHALL BE REFERRED TO THE ENGINEER FOR DECISION BEFORE PROCEEDING WITH THE WORK.
- 2. THE BILL OF QUANTITIES (BOQ) IS PROVIDED AS A GUIDE ONLY. THE CONTRACTOR IS TO REVIEW THIS BOQ AGAINST THE PLANS AND VERIFY QUANTITIES AS A PART OF THEIR DUE DII IGENCE IN TENDERING, ANY DISCREPANCIES ARE TO BE REFERRED TO ACS ENGINEERS FOR CLARIFICATION.
- 3. THE CONTRACTOR IS RESPONSIBLE FOR ACCURATELY ASCERTAINING THE LOCATION OF EXISTING UNDERGROUND AND OVERHEAD SERVICES PRIOR TO THE COMMENCEMENT OF WORKS.
- 4. ALL WORK UNDER THIS CONTRACT SHALL BE CARRIED OUT IN ACCORDANCE WITH REQUIREMENTS OF THE WORPLACE HEALTH AND SAFETY ACT 2011.

CONSTRUCTION NOTES

- THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ENGINEERS AND OTHER CONSULTANT'S DRAWINGS AND SPECIFICATIONS AND WITH OTHER SUCH WRITTEN
 INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCIES SHALL BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH THE
 WORK.
- 2. NO RESPONSIBILITY WILL BE TAKEN FOR DIMENSIONS OBTAINED BY SCALING THESE DRAWINGS.
- 3. ALL DIMENSIONS SHALL BE VERIFIED ON SITE BY THE CONTRACTOR WHO SHALL BE RESPONSIBLE FOR THEIR CORRECTNESS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURE AND NEIGHBORING STRUCTURES IN A SAFE AND STABLE CONDITION DURING CONSTRUCTION.
 NO PART SHALL BE OVER STRESSED.
- 5. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CURRENT LOCAL GOVERNMENT SPECS AND THE BY-LAWS AND ORDINANCES OF THE RELEVANT GOVERNMENT AUTHORITY.
- 6. THE CONTRACTOR SHALL PROVIDE TRAFFIC MANAGEMENT FOR THE DURATION OF CONSTRUCTION
- THE CONTRACTOR IS TO LOCATE, IDENTIFY AND ESTABLISH THE CONNECTIVITY OF ALL EXISTING SERVICES WITHIN THE LIMITS OF THE WORKS AND CONFIRM THIS INFORMATION WITH THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.
- 8. PROPERTY BOUNDARIES ARE SUBJECT TO CONFIRMATION BY FIELD SURVEY CARRIED OUT BY A REGISTERED SURVEYOR.
- 9. ALL WORK SHALL BE JOINED NEATLY TO EXISTING FEATURES.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MEASURING DEVICES, SAFETY EQUIPMENT AND MACHINERY REQUIRED TO CARRY OUT INSPECTIONS AS SPECIFIED OR REQUESTED.
- 11. THE CONTRACTOR SHALL RESTORE ALL EXTERNAL AREAS TO THE SITE, TO THEIR ORIGINAL CONDITION UPON COMPLETION OF THE WORKS.

FARTHWORKS

- THE CONTRACTOR IS TO STRIP THE CONSTRUCTION AREA OF ALL GRASS, SHRUBS, RUBBISH, DELETERIOUS MATERIAL AND UNSUITABLE TOPSOIL AS NOMINATED BY THE
 ENGINEER. DISPOSE OF THIS UNSUITABLE MATERIAL IS TO BE ON SITE. TOPSOIL APPROVED BY THE CLIENT FOR REUSE, IS TO BE STOCKPILED ON SITE AS DIRECTED. BULK
 EARTHWORKS IS TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL STANDARDS AND THE REQUIREMENTS OF AS3798.
- 2. THE CONTRACTOR SHALL PROVIDE DETAILS OF ALL TESTING TO THE ENGINEER PROGRESSIVELY THROUGH THE WORKS AND NOTIFY THE ENGINEER OF ANY NON-CONFORMANCES. ALL NON CONFORMING WORK IS TO BE RECTIFIED. PRIOR TO WORKS PROCEDURES, PROOF ROLL THE FILL AREA SUBGRADE. REMOVE SOFT AND OR COMPRESSIBLE ZONES AND REPLACE WITH SELECT SITE MATERIAL COMPACTED TO A DENSITY CONSISTENT WITH THAT NOTED FOR THE PROPOSED FILLING.
- 3. PROOF ROLLING NOMINATED SHALL BE CARRIED OUT USING A SINGLE AXLE HIGHWAY TRUCK WITH A REAR AXLE LOAD NOT LESS THAN 10 TONNES TYRES INFLATED TO 550kPa OR APPROVED EQUIVALENT. EQUIPMENT LABOUR AND LOADING REQUIRED FOR PROOF ROLLING IS TO BE PROVIDED BY THE CONTRACTOR.
- 4. ALL FILL UNDER FOOTINGS AND SLABS SHALL BE COMPACTED IN LAYERS NOT GREATER THAN 150mm TO 100% STANDARD COMPACTION FOR COHESIVE MATERIALS OR A DENSITY INDEX OF NOT LESS THAN 70% FOR NON COHESIVE MATERIALS.
- 5. TESTS SHALL BE CONDUCTED ON FILL AS REQUIRED BY THE CERTIFYING ENGINEER TO CONFIRM COMPACTION.
- 5. IT IS THE CONTRACTORS RESPONSIBILITY TO PROTECT THE SITE AND SURROUNDING AREAS FROM DAMAGE RESULTING FROM STORMWATER RUNOFF, TEMPORARY DIVERSION DRAINS AND OR OTHER DRAINAGE CONTROL DEVICES ARE TO BE IMPLEMENTED BY THE CONTRACTOR DURING CONSTRUCTION TO MINIMISE THE EFFECTS OF WEATHER
- 7. IMPORTED FILL MATERIAL SHALL BE GRANULAR FILL. ALL FILL MATERIAL PLACED ON THE SITE COMPRISING ONLY NATURAL
- EARTH AND ROCK IS TO BE FREE OF CONTAMINANTS (AS DEFINED BY SECTION 11 OF THE ENVIRONMENTAL PROTECTION ACT (EPA) 1994), NOXIOUS, HAZARDOUS,
 DELETERIOUS AND ORGANIC MATERIALS.
- 9. REFER TO LOCAL AUTHORITY DESIGN AND CONSTRUCTION MANUAL FOR ALLOWABLE CONSTRUCTION TOLERANCES.
- 10. IMPORTED FILL FOR BUILDING PAD SHALL MEET THE REQUIREMENTS OF AS3798 FOR IMPORTED FILL.
- 11. BUILDING PAD TO BE KEYED INTO NATURAL SURFACE AFTER TOPSOIL STRIP.

SURVEY

- 1. THE DATUM FOR ALL LEVELS IS THE AUSTRALIAN HEIGHT DATUM IN METRES AND PROJECTIONS ARE BASED ON GDA94 MGA ZONE 56 COORDINATE SYSTEM.
- 2. DETAILED SURVEY WAS CARRIED OUT BY SMK LAND SURVEYORS PTY LTD DRG REF: 21-007-1.
- 3. PROPERTY BOUNDARIES, WHERE SHOWN, ARE COMPILED FROM THE DCDB. THE ACCURACY OF PROPERTY BOUNDARIES IS NOT TO BE RELIED UPON.
- . SOME SERVICES HAVE BEEN EXPOSED AND LOCATED BUT OTHER SERVICE POSITIONS ARE DERIVED FROM SURFACE FEATURES ONLY. PRIOR TO EXCAVATION THE RELEVANT AUTHORITY SHOULD BE CONTACTED FOR DETAILED LOCATION OF ALL SERVICES.

EXCAVATION ADJACENT TO POWER POLES

- 1. POSSIBLE TRENCH SHORING REQUIREMENTS NEAR POWER POLES TO BE COORDINATED WITH ENERGEX AND THE APPROPRIATE APPROVALS TO BE OBTAINED FROM ENERGEX PRIOR TO CONSTRUCTION COMMENCEMENT.
- ANY TRENCHING REQUIREMENTS ADJACENT TO EXISTING POWER POLES SHALL HAVE THE POWER POLES ADEQUATELY SUPPORTED DURING TRENCHING
 AND BACKFILLING OPERATIONS. A CERTIFIED ENGINEERING ASSESSMENT OF THE COMPACTION OF BACKFILL MATERIAL IS TO BE PROVIDED TO AND
 ASSESSED BY ENERGEX TO ENSURE POLE STABILITY BEFORE REMOVAL OF ADDITIONAL SUPPORT.
- 3. ALL CONSTRUCTION WITHIN 3m OF OVERHEAD POWER LINES REQUIRE 'SAFETY ADVICE ON WORKING AROUND ELECTRICAL POSTS' FORM BS0001405F108 FROM ENERGEX.

4 THE EXTEN


- 1. THE EXTENT OF CLEARING OF VEGETATION SHALL BE KEPT TO THE ABSOLUTE MINIMUM NECESSARY TO UNDERTAKE THE WORKS.
- 2. SITE REVEGETATION AND ENVIRONMENTAL REQUIREMENTS SHALL BE CARRIED OUT TO THE SATISFACTION OF THE PRINCIPAL.
- 3. EROSION AND SEDIMENT CONTROLS ARE TO BE ESTABLISHED IN ACCORDANCE WITH DRAWINGS 08, 09 & 10.


PLANS AND DOCUMENTS referred to in the SDA APPROVAL





SDA approval: APC2022/005


				SURV	EY DATA	SANTREV PTY LTD					PO Box 554 Beaudesert QLD 4285	ACC	Г.,:	20010
				MAP GRID	DA94 GA-56	85 LOBB STREET, IPSWICH	GENERAL NOTES		(07) 55/4 3500	CIVIL ENVIRONMENTAL PROJE		1eers		
				HEIGHT ORIG	IN _	TILLEY ROAD POULTRY FARM	# FELD	ENGINEERING CERTIFIC	ATION (RPEQ) SIGNATURE	DATE	JOB NUMBER 210014			03
В	FOR APPROVAL	DJS	25.03.2021	SURVEY BO	OKS	TILLET ROAD POOLIKT PARM					210014		D	OF
Α	FOR APPROVAL	DJS	17.03.2021	DJS	03/2021	LOT 50, 2215 BOONAH-BEAUDESERT RD,					DRAWING NUMBER ACS-210014-P) A D A 2	D	11
FILE: GAS	REVISION/DETAILS VARPAYAPON INTENSIVATION THEFY OR POLICITY FARMADISSIN FILESCATES, FROM L. PAN DIVING PLOT TIME, 95/3/7001, LARDON BY HISPO LADRO	DWN	DATE	DES	DATE	BROMELTON QLD					ACS-210014-P	AU-03		11











FIELD INLET SEDIMENT TRAP

- DROP INLET WITH GRATE

GEOTEXTILE FILTER FABRIC

STAKES-

ROCK CHECK DAM

 1 LAYER OF WOVEN FILTER FABRIC WRAPPED OVER AND WIRED TO

KERB INLET SEDIMENT TRAP APPROVED PROPRIETARY SYSTEMS MAY BE USED IN LIEU OF THE DETAIL SHOWN

N.T.S.

PLACE.

DIRECTION OF FLOW POSTS @ 2.0m (MAX.) CENTRES STEEL PICKET OR 50 x 50 HARDWOOD 100mm OVERLAP OF FABRIC SEDIMENT CONTROL FABRIC TOP EDGE TO BE SUITABLY SUPPORTED BETWEEN POSTS. BOTTOM EDGE OF FABRIC TO BE SET IN TRENCH, BACKFILLED AND COMPACTED.

GULLY GRATE

Ø150 SLOTTED DRAIN PIPE

WRAPPED WITH GEOFABRIC.

PIPE TO BE FILLED WITH 20mm

SCREENINGS AND SUITABLY HELD IN

NOTE: WHERE TRAPPED LOW POINTS OCCUR IN THE SEDIMENT FENCE ADDITIONAL POSTS AND CHAIN WIRE BACKING IS TO BE PROVIDED TO PREVENT COLLAPSE OF THE STRUCTURE.

N.T.S.

SEDIMENT FENCE

EROSION AND SEDIMENT CONTROL MANAGEMENT PROGRAM:

CLEARING 1.1. INSTALL APPROPRIATE SAFETY FENCING AND SIGNAGE. 1.2. SEDIMENT FENCE, SEDIMENT BASINS AND DIVERSION DRAINS TO BE CONSTRUCTED AS REQUIRED.

EXISTING GRASSED AREAS TO REMAIN WHERE POSSIBLE. 1.3. TEMPORARY CONSTRUCTION ENTRY / EXIT AS REQUIRED. 1.5. CONSTRUCT UPSTREAM CLEAN WATER DIVERSION DRAINS IF

SUPERINTENDENT TO CONFIRM EXTENT OF CLEARING TO CONTRACTOR PRIOR TO COMMENCEMENT OF WORKS.

EARTHWORKS

2.1. SEDIMENT FENCES AND DIVERSION DRAINS TO BE CONSTRUCTED AS REQUIRED.

TEMPORARY LATERAL CONTOUR DRAINS TO BE INSTALLED IF SPECIFIED.

SEWER / ROOFWATER / STORMWATER / SERVICES

EXCAVATED MATERIAL TO BE PLACED ON HIGH SIDE OF TRENCH AND TO PROTECT PIPE WORK AND DIRECT SURFACE RUNOFF AWAY FROM EXCAVATIONS.

3.2. TOPSOIL AND HYDROMULCH AREAS IN ALLOTMENTS IMMEDIATELY AFTER COMPLETING THE SEWER AND ROOFWATER DRAINAGE CONSTRUCTION AND TURF OVER TRENCHES WHERE ADJACENT TO **EXISTING PROPERTIES.**

3.3. DEPRESS GROUND AROUND TEMPORARY FIELD INLETS TO CREATE SEDIMENT POND.

TURF OPEN DRAINS WHERE SHOWN. 3.4.

STOCKPILE

SEDIMENT FENCE TO BE ERECTED 5m FROM TOE OF BATTER ON LOW SIDE OF STOCKPILE.

> CUT OFF DRAIN ON HIGH SIDE TO DIRECT SURFACE RUNOFF AROUND STOCKPILE.

ROADWORKS

5.1. SEDIMENT FENCES TO ALLOTMENTS TO BE ERECTED. KERB INLET PROTECTION TO BE PROVIDED TO ALL GULLIES

UNLESS NOTED OTHERWISE. PLACE TURF FILTER STRIPS BEHIND KERB AND CHANNEL.

ALLOTMENTS

6.1. MULCH, TOPSOIL AND HYDROMULCH ALLOTMENTS AS DIRECTED.

SEDIMENT FENCES TO ALLOTMENTS TO BE ERECTED. 6.2.

6.3. COVERS TO GULLY GRATES TO BE REMOVED IF THE SUPERINTENDENT INDICATES THE GRASS STRIKE IS SUFFICIENT **EROSION AND SEDIMENT CONTROL** NOTES:

GENERAL

1.1.

ALL EROSION AND SEDIMENT CONTROLS TO BE IN ACCORDANCE WITH "BEST PRACTICE EROSION AND SEDIMENT CONTROL", INTERNATIONAL EROSION AND SEDIMENT CONTROL ASSOCIATION (IECA), AUSTRALASIA CHAPTER 2008 AND TO THE SATISFACTION OF THE SUPERINTENDENT.

12

NOTWITHSTANDING THE DESIGN SHOWN ON THE DRAWINGS, THE CONTRACTOR IS RESPONSIBLE TO IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES TO MINIMISE THE QUANTITY OF SEDIMENT LEAVING THE SITE.

1.3. TEMPORARY DRAINAGE CONTROL FLOW SHOULD BE DIVERTED AROUND THE WORK SITE WHERE POSSIBLE.

ALL DRAINAGE, EROSION AND SEDIMENT CONTROLS TO BE INSTALLED AND BE OPERATIONAL BEFORE COMMENCING **UP-SLOPE EARTHWORKS.**

ALL CONTROL MEASURES TO TO BE INSPECTED AT LEAST WEEKLY AND AFTER SIGNIFICANT RUNOFF PRODUCING STORMS.

AT ALL TIMES THE CONTRACTOR SHALL MONITOR THE PREVAILING WEATHER CONDITIONS AND PROTECT AND DOWNSTREAM CONSTRUCTION GULLY INLETS.

CONTROL MEASURES MAY BE REMOVED WHEN ON-SITE EROSION 1.7. IS CONTROLLED AND 70% PERMANENT SOIL COVERAGE IS

1.8. IN AREA WHERE RUNOFF TURBIDITY IS TO BE CONTROLLED, EXPOSED SURFACES TO BE EITHER MULCHED, COVERED WITH EROSION CONTROL BLANKETS OR TURFED IF EARTHWORKS ARE EXPECTED TO BE DELAYED FOR MORE THAN 14 DAYS.

OBTAINED OVER ALL UPSTREAM DISTURBED LAND.

1.9. PONDED RAINFALL SHALL BE PUMPED THROUGH A SEDIMENT FENCE LOCATED ON THE SITE BEFORE DISCHARGING INTO THE

DOWNSTREAM STORMWATER SYSTEM. ALL OPEN DRAINS AND BATTERS ARE TO BE TOPSOILED AND HYDROMULCHED WITHIN 7 DAYS OF COMPLETION.

TURF STRIPS ARE TO BE PROVIDED OVER SEWER / ROOFWATER LINES WHERE ADJACENT TO EXISTING PROPERTIES.

ALL SEDIMENT CONTROL DEVICES SHALL BE MONITORED, CLEANED AND / OR REPAIRED WHENEVER THE CAPACITY OF THE DEVICE FALLS BELOW 75%.

SEDIMENT FENCE

2.2.

2.1. NOT TO BE LOCATED IN AREAS OF CONCENTRATED FLOW.

NORMALLY LOCATED ALONG THE CONTOUR WITH A MAXIMUM CATCHMENT AREA OF 0.6ha PER 100m LENGTH OF FENCE.

2.3. WOVEN FABRICS ARE PREFERRED, NON-WOVEN FABRICS MAY BE USED ON SMALL WORK SITES, IE. OPERATIONAL PERIOD LESS THAN 6 MONTHS OR ON SITES WHERE SIGNIFICANT SEDIMENT RUNOFF IS NOT EXPECTED.

WHERE FENCES NEED TO BE LOCATED ACROSS THE CONTOUR THE LAYOUT SHALL CONFORM TO TYPICAL LAYOUT ACROSS

2.5. FENCES ARE REQUIRED 2m MINIMUM FROM TOE OF CUT OR FILL BATTERS, WHERE NOT PRACTICAL ONE FENCE CAN BE AT THE TOE WITH A SECOND FENCE 1m MINIMUM AWAY. FENCE SHOULD NOT

BE LOCATED PARALLEL WITH TOE IF CONCENTRATION OF FLOW WILL OCCUR BEHIND AT FENCE

TEMPORARY CONSTRUCTION ENTRY / EXIT ADJACENT STORMWATER RUNOFF TO BE DIVERTED AWAY FROM

ENTRY / EXIT. WHEEL WASH OR SPRAY UNIT MAY BE REQUIRED DURING WET

WEATHER. FIELD INLET SEDIMENT TRAP

A STABILISED BYPASS OVERLAND FLOW PATH SHOULD EXIST

ADJACENT TO THE FIELD INLET.

WATER LEVEL CONTROL PERIMETER BANKS MAY BE REQUIRED.

KERB INLET SEDIMENT TRAP

INLETS TO HAVE SILT PROTECTION IN ACCORDANCE WITH KERB INLET SEDIMENT TRAP DETAIL AT LOCATIONS SHOWN OR AS DIRECTED BY THE SUPERINTENDENT

ROCK CHECK DAM

CATCHMENT AREA LIMITED TO 4ha.

USE IN MINOR OPEN DRAINS ONLY FOR VELOCITY CONTROL, SEDIMENT COLLECTION IS A SECONDARY PURPOSE.

STRAW BALES ARE ONLY EMERGENCY USE ONLY.

SAFETY ISSUES MUST BE CONSIDERED AT ALL TIMES, INCORPORATE TRAFFIC CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT ..

WHERE SEWERS HAVE A GRADE OF 1 in 20 OR STEEPER, BULKHEADS SHALL BE CONSTRUCTED IN RELEVANT AUTHORITIES BEFORE COMMENCING WORKS.

SEWERS SHALL BE DISUSED / ABANDONED IN ACCORDANCE WITH PROCEDURES SET OUT IN THE SEQ CODE

ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.

PLANS AND DOCUMENTS referred to in the SDA APPROVAL

SDA approval: APC2022/005

FOR APPROVAL

© 2022 Urban Engineering Solutions Pty. Ltd. | Client This design and drawing remain the property of Urban Engineering Solutions Pty. Ltd. and is not to be COMPOST REMOVED Q.T. 02.08.23 reproduced either in whole or in part without the written ISSUED FOR APPROVAL Q.T. 28.07.22 permission of Urban Engineering Solutions Pty. Ltd. Q.T. 15.07.22 P1 PRELIMINARY ISSUE Description

SOLUTIONS CIVIL ENGINEERING	S DESIGN AND DOCUMENTATION JSTRIAL — COMMERCIAL TOURISM PH: 0488 998 775 E: dpayne@urbanenginee	ring.com at
_	<u> </u>	


	Drawn	Q.T.	
7	Designed	D.P.	Ti
J.	Passed	Deaufy-	
	Checked	Deanpay	


POULTRY FARM - 75 TILLEY RD, BROMELTON **EROSION AND SEDIMENT CONTROL**


C0284-OW-EC-001


Print Scale 12


NOTES AND TYPICAL DETAILS DO NOT SCALE FROM DRAWING Date 10 11


























STORMWATER MANAGEMENT PLAN

PROPOSED POULTRY FARM EXTENSION 75 TILLEY ROAD – BROMELTON

PLANS AND DOCUMENTS referred to in the SDA APPROVAL



SDA approval: APC2022/005



Prepared By:

MPN CONSULTING PTY LTD

Level 5 39 Sherwood Road Toowong Queensland 4066 • Australia



SITE BASED MANAGEMENT PLAN

POULTRY FARM DEVELOPMENT

PREPARED By:

ALLANS CREEK PTY LTD 75 TILLEY ROAD BROMELTON, QLD 4285

PLANS AND DOCUMENTS referred to in the SDA APPROVAL



SDA approval: APC2022/005

BARRY SHONHAN 75 TILLEY ROAD BROMELTON QLD 4285 P: 0409 273 702

E: <u>barry@allanscreekpoultry.com.au</u>